

Letting September 19, 1927.

Honorable County Commissioners
Tulsa County, Oklahoma.

Gentlemen:

The undersigned, having examined the plans and specifications, the location and character of the work proposed to be done and performed in the construction of the herein listed Bridges and Culverts, proposes to furnish all labor, materials and equipment and to complete the same according to the plans and specifications and to the stakes and under the direction of the County Engineer or his duly authorized representatives, which price as bid includes all excavation and the structure complete and in place (Oklahoma State Standard Specifications to govern) the following structures at the unit item prices set opposite, viz, to-wit:

GROUP NO 1.

DAWSON TOWNSHIP

MEMORIAL DRIVE

NORTH OF FEDERAL DRIVE

Bet. Secs. 35-36, T 20 N., R 13 E. 2' x 2' x 26' BC - 5 Box Culvert	Sta. 7 / 00 Drainage Area 10 A Fast Rolling		
1:2:4 Concrete	7.72 C Y @ \$16.50 Per C Y	\$127.38	
Reinforcing Steel	650. Lbs. @ .05 Per Lb	32.50	
	Total	\$159.88	
Bet. Secs. 35-36, T 20 N. R 13 E. 3' x 2' x 26' BC - 5 Box Culvert	Sta. 14 / 42 Drainage Area 20 A Fast Rolling		
1:2:4 Concrete	9.1 C Y @ \$16.50 Per C Y	\$150.15	
Reinforcing Steel	759. Lbs @ .05 Per Lb.	37.95	
	Total	\$188.10	
Bet. Secs. 35-36, T 20 N. R 13 E. 3' x 2' - 6" x 26' B C 5 Box Culv. Culvert Floor on Grade - No paving rests - 2" Crown 18' wide.	Sta. 38 / 70 Drainage Area 35 A Fast Rolling.		
1:2:4 Concrete	10.6 C Y @ \$16.50 Per C Y	\$174.90	
Reinforcing Steel	807. Lbs. @ .05 Per Lb.	40.35	
	Total	\$215.25	
Bet. Secs. 35-36, T 20 N., R 13 E. 6' x 3' x 26' BC - 5 Box Culvert Culvert Floor on Grade - No paving rests - 2" Crown 18' Wide.	Sta. 49 / 10 Drainage Area 110 A Fast Rolling		
1:2:4 Concrete	20.9 C Y @ \$16.50 Per CY	\$344.85	
Reinforcing Steel	1611. Lbs @ .05 Per Lb.	80.55	
	Total	425.40	
Bet. Secs. 25-26, T 20 N., R 13 E., Double 10' x 4' x 26' BC Box Culv. Culvert Floor On Grade - No paving rests - 2" Crown, 18' wide.	Sta. 60 / 03 Drainage Area 865 A Fast Rolling.		
1:2:4 Concrete	68.9 C Y @ \$16.50 Per C Y	1,136.85	
Reinforcing Steel	6018. Lbs. @ .05 Per Pb.	300.90	
	Total	1,437.75	
Bet. Secs. 25-26, T 20 N., R 13 E. Double 6' x 26' BC A Box Culv. Culvert Floor on Grade. - No Paving Rests - 2" Crown 18' wide.	Sta. 74 / 86 Drainage Area 275 A Fast Rolling.		
1:2:4 Concrete	37.0 C Y @ \$16.50 Per CY	610.50	
Reinforcing Steel	3086. Lbs. @ .05 Per Lb.	154.30	
	Total	764.80	
Bet. Secs. 25-26, T 20 N., R 13 E., 3' x 2' x 26' BC - 5 Box Culvert Culvert Floor on Grade - No paving rests. - 2" Crown, 18' Wide	Sta. 85 / 55 Drainage Area 30 A Fast Rolling.		
1:2:4 Concrete	9.4 C Y @ \$16.50 Per C Y	\$155.10	
Reinforcing Steel	759. Lbs. @ .05 Per Lb.	37.95	
	Total	\$193.05	
Bet. Secs. 23-24, T 20 N., R 13 E. 4' x 2' x 26' BC - 5 Box Culvert	Drainage Area 35 A Fast Rolling.		
1:2:4 Concrete	11.3 C Y @ \$16.50 Per C Y	\$186.45	
Reinforcing Steel	977 Lbs. @ .05 Per Lb.	48.85	
	Total	235.30	