

Bet. Secs. 23-24, T 20 N. R 13 E. 4' x 2' x 26' BC - 5 Box Culvert		Drainage Area 35 A Fast Rolling.		
1:2:4 Concrete	11.3 C Y	\$16.50 Per C Y	\$186.45	
Reinforcing Steel	977. Lbs	.05 Per Lb.	48.85	
		Total	\$235.30	

Bet. Secs. 23-24, T 20 N., R 13 E. 3' x 2' x 26' BC - 5 Box Culvert		Drainage Area 20 A. Light Hilly		
1:2:4 Concrete	9.1 C Y	\$16.50 Per C Y	\$150.15	
Reinforcing Steel	759. Lbs.	.05 Per Lb.	37.95	
		Total	\$188.10	

In Sec. 23, T 20 N., R 13 E. 3' x 3' x 26' BC - 5 Box Culvert Culvert Floor on Grade - No Paving Rests - 2" Crown 18' Wide.				
1:2:4 Concrete	9.4 C Y	\$16.50 Per C Y	\$155.10	
Reinforcing Steel	759. Lbs.	.05 Per Lb.	37.95	
		Total	193.05	

In Sec. 23, T 20 N. R 13 E. 10' x 5' x 26' BC 5 Box Culvert Culvert Floor on Grade - No Paving Rests - 2" Crown 18' wide.		Drainage Area 380 A Fast Rolling.		
1:2:4 Concrete	43.4 C Y	\$16.50 Per C Y	\$716.10	
Reinforcing Steel	3440. Lbs.	.05 Per Lb.	172.00	
		Total	\$888.10	

HARVARD AVENUE

NORTH OF FRISCO RAILWAY.

Bet. Secs. 32-33, T 20 N., R 13 E. 8' x 3' x 26' BC - 5 Box Culvert		Drainage Area 175 A. Fast Rolling.		
1:2:4 Concrete	26.5 C Y	\$16.50 Per C Y	\$437.25	
Reinforcing Steel	2323. Lbs.	.05 Per Lb.	116.15	
		Total	\$553.40	

NORTH CINCINNATI

Bet. Secs. 23-24, T 20 N., R 12 E., 2' x 2' x 33' BC - 5 Box Culvert		Sta 11 / 80		
1:2:4 Concrete	9.0 C Y	\$16.50 Per C Y	\$148.50	
Reinforcing Steel	800. Lbs.	.05 Per Lb.	40.00	
		Total	\$188.50	

Bet. Secs. 23-24, T 20 N., R 12 E. Ext. 6 x 4 x 20.4' Box to 6 x 4 x 34.4'		Sta. Ext. 6' -0" On WestC) BC -5 " 8' -0" On East)		
1:2:4 Concrete	17.0 C Y	\$16.50 Per C Y	\$280.50	
Reinforcing Steel	1200. Lbs.	.05 Per Lb.	60.00	
		Total	\$340.50	

TOTAL FOR GROUP NO 1. \$6,206.48

LYNN LANE TOWNSHIP

Bet. Secs. 23-26, T 19 N., R 13 E. Sta. 232 / 75 East 41st. Street 8' x 6' x 30' BC - 5 Box Culvert. Culvert Floor On Grade No Paving Rests. 2" Crown, 18' Wide.		Drainage Area 260 A Fast Rolling.		
1:2:4 Concrete	46.2 C Y	\$16.50 Per C Y	\$762.30	
Reinforcing Steel	3300. Lbs.	.05 Per Lb.	165.00	
		Total	\$927.30	

Bet. Secs. 21-28, T 19 N., R 13 E. Sta. 133 / 94 East 41st. Street Double 8' x 9' x 24' BC 5A Box Culv. Culvert Floor on Grade - With Paving Rests and 2" Crown 18' Wide.		Drainage Area 1500 A Fast Rolling.		
1:2:4 Concrete	94.0 C Y	\$16.50 Per C Y	\$1,551.00	
Reinforcing Steel	6500. Lbs.	.05 Per Lb.	325.00	
Handrail, Complete	40. L F	3.50 Per L F	120.00	
Including Posts, Reinf. and Precast Rail as per plan		Total	\$1,996.00	

Bet. Secs. 12-13, T 19 N., R 13 E. On East 21st. Street. 6' x 6' x 30' BC - 5 Box Culvert		Drainage Area 300 A Fast Rolling.		
1:2:4 Concrete,	38.0 C Y	\$16.50 Per C Y	\$627.00	
Reinforcing Steel	2457. Lbs.	.05 Per Lb.	122.85	
		Total	\$749.85	

GRAND TOTAL FOR GROUP NO 2. \$3,673. 15

BOLES TOWNSHIP.

In Sec. 11, T 18 N., R 14 E. 8' x 3' x 30' BC - 5 Box Culvert		Near North Line of Broken Arrow.		
1:2:4 Concrete	29.5 C Y	\$16.50 Per C Y	\$486.75	
Reinforcing Steel	2620 Lbs.	.06 Per Lb.	\$157.20	
		Total	\$643.95	