

Bet. Sec. 26-27, T 18 N., R 12 E.		Sta 352 / 55	
5 x 3 x 30' BC - 5 Culvert		Dr. Area 100 A Fast Rolling.	
Build paving rests and 2" Crown			
1:2:4 Concrete	19.0 C Y @ \$19.00 per C Y		\$ 361.00
Reinforcing Steel	1560 Lbs. @ .051/4 Per Lb		81.90
	Total		\$ 442.90
Bet. Sec. 26-27, T 18 N., R 12 E.		Sta. 369 / 08	
14 x 8.4 x 21.3' S T Culvert			
7' - 3" on Left.) As per plan.			
Extend 1' - 6" on Right)			
1:2:4 Concrete	55.6 C Y @ \$20.00 per C Y		\$1,112.00
Reinforcing Steel	4500. Lbs @ .051/4 Per Lb.		236.25
	Total		\$1,348.25
Between Sec. 26-27, T 18 N., R 12 E.		Sta. 378 / 00	
3 x 2-6" x 30' BC - 5 Culvert.		Dr. Area 30 A Light Hilly.	
Build paving rests and 2" crown.			
1:2:4 Concrete	12.4 C Y @ \$ 19.00 per C Y		\$ 235.60
Reinforcing Steel	960 Lbs @ .51/2 per Lb.		52.80
	Total		\$ 288.40
Bet. Sec. 34-35, T 18 N., R 12 E.		Sta. 392 / 50	
3 x 2 x 34' BC - 5 Culvert.		Dr. Area 15 A. Light Hilly.	
1:2:4 Concrete	11.0 C Y @ \$19.00 per C Y		\$ 209.00
Reinforcing Steel	1000. Lbs. @ .051/2 Per Lb		55.00
	Total		\$ 264.00
Bet. Sec. 34-35, T 18 N., R 12 E.		Sta. 405 / 77	
3 x 2 x 30' BC - 5 Culvert.		Dr. Area 15 A. Light Hilly.	
Build Paving Rests and 2" Crown.			
1:2:4 Concrete	11.2 C Y @ \$19.00 per C Y		\$ 212.80
Reinforcing Steel	900 Lbs. @ .051/2 Per Lb.		49.50
	Total		\$ 262.30
Bet. Sec. 34-35, T 18 N., R 12 E.		Sta. 423 / 06	
11 x 6 x 20' S.T. Culvert			
Extend to 11 x 6 x 30') 5' on Left			
) 5' on Right			
1:2:4 Concrete	31.0 C Y @ \$21.00 Per C Y		\$ 651.00
Reinforcing Steel	2000 Lbs. @ .051/4 per Lb.		105.00
	Total		\$ 756.00
Bet. Sec. 34-35, T 18 N., R 12 E.		Sta. 427 / 33	
10 x 5 x 30' BC - 5 Culvert		Dr. Area 410 A. Fast Rolling.	
Build Paving rests and 2" Crown.			
1:2:4 Concrete	48.8 C Y @ \$20.00 Per C Y		\$ 976.00
Reinforcing Steel	3920 Lbs. @ .051/4 per Lb.		205.80
	Total		\$1,181.80
Bet. Sec. 2-3, T 17 N., R 12 E.		Sta. 456 / 71	
3 x 2 x 30' BC - 5 Culvert.		Dr. Area 15 A., Fast Rolling.	
Building Paving rests and 2" Crown.			
1:2:4 Concrete	11.2 C Y @ \$19.00 per C Y		\$ 212.80
Reinforcing Steel	900 Lbs. @ .051/2 Per Lb.		49.50
	Total		\$ 262.30
Bet. Sec. 2-3, T 17 N., R 12 E.		Sta. 468 / 13	
2 x 2 x 56' - BC 6 Culvert.		Dr. Area 12 A. Fast Rolling.	
(Heavy Excavation)			
1:2:4 Concrete	13.8 C Y @ \$24.00 per C Y		\$ 331.20
Reinforcing Steel	1260 Lbs. @ .051/2 per Lb.		69.30
	Total		\$ 400.50
Bet. Sec. 2-3 T 17 N., R 12 E.		Sta. 471 / 88	
2 x 2 x 40' BC - 5 Culvert.		Dr. Area 2 A. Light Hilly.	
1:2:4 Concrete	10.6 C Y @ \$19.00 Per C Y		\$ 201.40
Reinforcing Steel	960 Lbs. @ .051/2 Per Lb.		52.80
	Total		\$ 254.20
Bet. Sec. 2-3, T 17 N., R 12 E.		Sta. 478 / 75	
3 x 2 x 56' BC - 6 Culvert		Dr. Area 25 A. Light Hilly.	
1:2:4 Concrete	16.4 C Y @ \$24.00 per C Y		\$ 393.60
Reinforcing Steel	1490 Lbs. @ .051/2 Per Lb.		81.95
	Total		\$ 475.55
NOTE: New Culvert built 50 feet south of old culvert. Old culvert to remain in place.			
Bet. Sec. 2-3, T 17 N., R 12 E.,		Sta. 481 / 50	
2 x 2 x 52 BC - 6 Culvert		Dr. Area 5 A. Light Hilly.	
1:2:4 Concrete	12.8 C Y @ \$21.10 per C Y		\$ 270.08
Reinforcing Steel	1220 Lbs. @ .051/2 Per Lb.		67.10
	Total		\$ 337.18
NOTE: New Culvert built 15 feet south of old Culvert. Old Culvert to remain in place.			