

3 work until the Tax protest suits now pending in the Supreme Court of the State of Oklahoma are settled in favor of Tulsa County, and funds thus released are available for the payment of said work.

Upon failure to complete within the time limit as proposed, we agree to the provisions as embodied in the Oklahoma State Standard Specifications respecting failure to complete within the specified time as bid.

When mutually agreed to by and between your Honorable Board and ourselves, this proposal may be considered for extension to additional work of the same character and upon the same highway and as a continuation of the work herein bid upon as though the same were herein originally contained and set out.

Certified Check or Bidder's Bond amounting to \$1,000.00 being approximately 10% of the sum bid and conforming to the "Notice to Contractors" and specification provisions, is here to attached.

NOTE: Attention is called to the provision embodied in the published "Notice to Contractors" that proposal forms must be on forms prepared by the County Engineer.

Respectfully submitted this 26th. day of June, 1930.

W L MOODY. Contractor.

PROPOSAL NO. 5

The following Bids were received for the construction of Drainage Structures in Owasso and Dawson Townships:

W L MOODY	\$12,181.72
J H Maxwell	14,664.31
Standard Paving Co.	12,500.04
McConnell and Roop	12,323.46
S E Gray	15,087.57

Upon motion of Mr. Hedgecock seconded by Mr. Dickey, the award of the contract was made to W L MOODY, for the construction of Drainage Structures in Owasso and Dawson Twps. he being the lowest and best bidder therefor, upon the following bid:

PROPOSAL NO. 5.
RESOLUTION No. 4.
Letting June 26th. 1930.

Honorable Board of County Commissioners,
Tulsa County, Oklahoma.

Gentlemen:

The undersigned, having examined the plans and specifications, the location and character of the work proposed to be done and performed in the construction of the herein listed DRAINAGE STRUCTURES, proposes to furnish all labor, materials, (except R C Pipe which is specifically noted as being furnished at site of work by Tulsa County) and equipment, and to complete the same according to the plans and specifications and to the stakes and under the direction of the County Engineer or his duly authorized representatives, which price as bid includes all excavation and the structure complete and in place (Oklahoma State Standard Specifications to govern, with the special provision that only Limestone Coarse Aggregate will be used), the following structures at the unit item prices set opposite viz, to-wit:

OWASSO TOWNSHIP.

APPROXIMATE QUANTITIES.

(1) Bet Secs. 23-24, T 21 N., R 13 E.

18' x 2' x 20' I BM Conc. Culvert.
Extend both ends to 18' x 2' x 32' Culvert
Deepen stream above and below to 3' -6"

1:2:3 Concrete (Floor)	18.73 C Y @ \$17.00 per C Y	\$	318.41
1:2:4 Concrete (Abuts)	18.79 C Y @ \$17.00 per C Y		319.43
Reinforcing Steel	3488 Lbs. @ \$.04 per Lb.		139.52
Structural Steel	4982 Lbs. .04 Per Lb.		199.28
Handrail complete			
Reinforc. Concrete	41 L F @ \$2.00 per L F		82.00
Floor Drains			
2 1/2" Pipe	4. L F @ \$.50 per L F		2.00
	TOTAL	\$	1,060.64

(2) Bet. Secs 23-24 T 21 N., R 13 E.

10' x 3' x 18' Slab Top Culvert.
Extend both ends to 10' x 3' x 32' Culvert.

1:2:4 Concrete	19.49 C Y @ \$17.00 per C Y	\$	331.33
Reinforcing Steel	1635 Lsb. @ \$.04 per Lb.		65.40
	TOTAL	\$	396.73