

(3)	In Sec. 33, T 21 N., R 13 E. 8' x 3' x 36' BC 5 Box Culvert 1:2:4 Concrete Reinforcing Steel	33.43 C Y @ \$16.80 per C Y 3065 Lbs. @ \$.04 per Lb.	Dr. Area 130 A. C=0.6 \$ 561.62 122.60 TOTAL \$ 684.22
(4)	Bet. Secs. 21-28, T 21 N., R 13 E. 3' x 2' x 30' BC 5 Box Culvert 1:2:4 Concrete Reinforcing Steel	9.78 C Y @ \$17.00 per C Y 851 Lbs. @ \$.04 per Lb.	Dr. Area 20 A. C=0.6 \$ 166.26 34.04 TOTAL \$ 200.30
(5)	Bet. Secs. 21-28, T 21 N. R 13 E. 4' x 3' x 30' BC 5 Box Culvert 1:2:4 Concrete Reinforcing Steel	14.90 C Y @ \$17.00 per C Y 1269 Lbs. @ \$.04 per Lb.	Dr. Area 40 A. C=0.6 \$ 253.30 50.76 TOTAL \$ 304.06
(6)	Bet. Secs. 21-28, T 21 N., R 13 E. 3' x 2' x 30' BC 5 Box Culvert. 1:2:4 Concrete Reinforcing Steel	9.78 C Y @ \$17.00 per C Y 851 Lbs. @ \$.04 per Lb.	Dr. Area 20 A. C=0.6 \$ 166.26 34.04 TOTAL \$ 200.30
(7)	Bet. Secs. 22-27, T 21 N., R 13 E. 4' x 2' x 30' BC 5 Box Culvert. 1:2:4 Concrete Reinforcing Steel	12.27 C Y @ \$17.00 per C Y 1099 Lbs. @ \$.04 per Lb.	Dr. Area 30 A C=0.6 \$ 208.59 43.96 TOTAL \$ 252.55
(8)	Bet. Secs. 22-27, T 21 N., R 13 E. Double 8' x 7' x 30' BC 5 A Box Culv. 1:2:4 Concrete Reinforcing Steel	82.85 C Y : \$16.80 per C Y 6531 Lbs. @ \$.04 Per Lb.	Dr. Area 900 A. C=0.6 Channel Change. \$ 1,391.88 261.24 TOTAL \$ 1,653.12
(9)	Bet. Secs. 23-26, T 21 N. R 13 E. 5' x 2' x 30' BC 5 Box Culvert 1:2:4 Concrete Reinforcing Steel	14.56 C Y @ \$17.00 per C Y 1324 Lbs. @ \$.04 per Lb.	Dr. Area 40 A. C=0.5 \$ 247.52 52.96 TOTAL \$ 300.48
(10)	Bet. Secs. 23-26, T 21 N. R 13 E. 32'-24" R C Pipe Culvert. County will furnish pipe at site of work. Installing 24" R C Pipe 1:2:4 Concrete Reinforcing Steel	32 L F @ \$1.25 per L F 2.08 C Y : \$18.00 per C Y 56 Lbs. @ \$.04 per Lb.	\$ 40.00 37.44 2.24 TOTAL \$ 79.68
(11)	Bet. Secs. 28-33, T 21 N., R 13 E. 36'-24" R C Pipe Culvert County will furnish pipe at site of work. Installing 24" R C Pipe 1:2:4 Concrete Reinforcing Steel	36 L F @ \$1.25 Per L F 2.08 C Y @ \$18.00 per C Y 56 Lbs. @ \$.04 per Lb.	\$ 45.00 37.44 2.24 TOTAL \$ 84.68
(12)	Bet. Secs. 29-32, T 21 N., R 14 E. 4' x 2' x 30' BC 5 Box Culvert 1:2:4 Concrete Reinforcing Steel	12.27 C Y @ \$17.00 per C Y 1099 Lbs. @ \$.04 per Lb.	Dr. Area 30 A. C=0.6 \$ 208.59 43.96 TOTAL \$ 252.55
(13)	Bet. Secs. 29-32, T 21 N., R 14 E., 3' x 2' x 30' BC 5 Box Culvert 1:2:4 Concrete Reinforcing Steel	9.78 C Y @ \$17.00 per C Y 851 Lbs. @ \$.04 per Lb.	Dr. Area 20 A C=0.6 \$ 166.26 34.04 TOTAL \$ 200.30
TOTAL FOR CONSTRUCTION OF DRAINAGE STRUCTURES IN OWASSO TOWNSHIP			\$ 5,669.61