his office, and records of former Justices' of the Peace in his possession. And,

BE IT FURTHER RESOLVED, That the Hon State Examiner & Inspector be and he is hereby instructed to audit the records of all Justices of the Peace in the City of Tulsa, affected by the provision of said Senate Bill No.113.

The vote on this motion to adopt the Resolution was as follows:

Ayes:

Geo.E.Gilmore

F.M.Wooden

Ira Short.

The Resolution having been adopted was ordered made of record and a certified copy sent to Hon. Fred Parkinson, State Examiner & Inspector, Oklahoma City, Oklahoma.

Adjournment ordered until 2 o'clock P.M.

Meeting was called to order, with all members present, and the first matter coming on for consideration was the openeing of bids for the construction of bridges over Delaware Creek, where the same crosses Mile 2 of Section "D" Tulsa County Atate Highway, and also for the construction of a Bridge over Polecat Bridge where the same crosses the line between Sections 25 and 30, Township 18 North and on the Range line between Ranges 12 and 13 East.

ENGINEER'S ESTIMATE Delaware Creek Bridge.

•		
71.4 C.Y. 1:2:3 Concrete 177.5 C.Y. 1:2:4 Conc. 23085 Lbs.Reinf.Steel 53285 Lbs.Struct'l Steel 928 L.F.Oak Piles 67 C.Y. Wet Excavation 272 C.Y. exc. 400 L.F. 3½" Pipe Rail	@ 22.00 @ 21.00 @ 00.055 @ 00.06 @ 1.00 @ 5.00 @ 1.25 @ 0.80	\$ 1570.80 3727.50 1269.57 3197.10 928.00 335.00 340.00 320.00
Dismantling old Bridge Removing concrete pavement neel 118 Sq.Yds. @ \$3.50	Total .cessary and repaving	\$11687.97 500.00 413.00
	Grand Total	\$12700.97

Bids may be considered when not in excess of 5% more than the sum of \$12,700.97, or a total of 13336.02

ESTIMATE FOR POLE CAT CREEK BRIDGE.

18540 Lbs. Steel in tubes in place 130150 Lbs. Struct'l Steel erected 2807 Lbs. Reinforcing Steel in piers 11387 Lbs. Reinforcing Steel in floors 1610 Lbs. Reinforcing in Abut's 80.7 C.Y. Concrete in floor 91 C.Y. Concrete in Piers 32.8 C.Y. Concrete in Abut's 55 C.Y. Wet Excavation 108 C.Y. Dry Excavation	@ 00.06 @ 00.675 @ 00.055 @ 00.055 @ 22.00 @ 21.00 @ 21.00 @ 1.00	Total	\$ 1112.40 8785.12 154.39 626.28 88.55 1775.40 1911.00 688.80 275.00 108.00 \$15524.94
257Sq.Yds. 1:2:3, 18 ft 64X84X64" Concrete Payement including Exc.	@ 3.00°		

771.00 Dismantling old bridge to readside for hauling away by trucks

Total Est. of Cost.

750.00 \$17045.94

Office of County Engineer, Tulsa, Oklahoma. March 5th. 1923.

Dan W. Patton, County Engineer. The following named bidders submitted bids, with the total amount of bids listed:

NAME	DELAWARE	CREEK	BRIDGE	TOTAL AMOUNT BID
Killough Bros. Froebe-Gravelle-Hamblin Pioneer Construction Co. E.C. Bancroft E.G. Fike & Co.	•			13,060.70 16,708.12 13,020.19 13,180.24 11,804.19
i e e e e e e e e e e e e e e e e e e e	ውለቸ.ፑሮላለጥ	לינו ינוס ח	DDTDAM	·

POLECAT CREEK BRIDGE.

Southwestern Bridge and culvert Co.