

WILLOW SPRINGS TOWNSHIP.

- (1) Bet. Secs. 1-36, T 17-18, N., R 14 E. Dr. Area 100 A C = 0.6
6' x 3' x 26' BC 5 Box Culvert.
- | | | | |
|-------------------|-----------------------------|----|--------|
| 1:2:4 Concrete | 20.06 C Y @ \$16.80 Per C Y | \$ | 337.00 |
| Reinforcing Steel | 1611 Lbs. @ .04 Per Lb. | | 64.44 |
| | TOTAL | \$ | 401.44 |
- (2) Bet. Secs. 2-35, T 18-17, N., R 14 E. Dr. Area 40 A. C = 0.5
4' x 2' x 29' BC 5 Box Culvert.
- | | | | |
|-------------------|-----------------------------|----|--------|
| 1:2:4 Concrete | 11.98 C Y @ \$17.00 per C Y | \$ | 203.66 |
| Reinforcing Steel | 1069 Lbs. @ .04 Per Lb. | | 42.76 |
| | TOTAL | \$ | 246.42 |
- (3) Bet. Secs. 2-35, T 17-18 N., R 14 E. Dr. Area 50 A. C = 0.4
4' x 2' -29' BC 5 Box Culvert.
- | | | | |
|-------------------|-----------------------------|----|--------|
| 1:2:4 Concrete | 11.98 C Y @ \$17.00 per C Y | \$ | 203.66 |
| Reinforcing Steel | 1069 Lbs. @ \$.04 per Lb. | | 42.76 |
| | TOTAL | \$ | 246.42 |
- TOTAL FOR CONSTRUCTION OF
DRAINAGE STRUCTURES IN
WILLOW SPRINGS TOWNSHIP \$ 896.28

BIXBY TOWNSHIP

- (1) Bet. Secs. 21-28, T 17 N., R 13 E. Dr. Area 10 A C = 0.5
28' -24" R C Pipe Culvert
County will furnish pipe at site of work.
- | | | | |
|-------------------------|----------------------------|----|-------|
| Installing 24" R C Pipe | 28 L F @ \$1.25 Per L F | \$ | 35.00 |
| 1:2:4 Concrete | 2.08 C Y @ \$18.00 per C Y | | 37.44 |
| Reinforcing Steel | 56 Lbs. @ .04 Per Lb. | | 2.24 |
| | TOTAL | \$ | 74.68 |
- (2) Bet. Secs. 21-28, T 17 N., R 13 E. Dr. Area C = 0.5
3' x 2' -6" x 26' BC 5 Box Culvert.
- | | | | |
|-------------------|------------------------------|----|--------|
| 1:2:4 Concrete | 10.06 C Y @ \$ 17.00 per C Y | \$ | 171.02 |
| Reinforcing Steel | 807. Lbs. @ \$.04 per Lb. | | 32.28 |
| | TOTAL | \$ | 203.30 |
- (3) Bet. Secs. 21-28, T 17 N., R 13 E. Dr. Area 45 A. C = 0.5
4' x 2' -6" x 26' BC 5 Box Culvert
- | | | | |
|-------------------|-----------------------------|----|--------|
| 1:2:4 Concrete | 12.30 C Y @ \$17.00 per C Y | \$ | 209.10 |
| Reinforcing Steel | 1025 Lbs. @ .04 per Lb. | | 41.00 |
| | TOTAL | \$ | 250.10 |
- (4) Bet. Secs. 21-28, T 17 N., R 13 E. Dr. Area 450 A C = 0.5
10' x 5' x 26' BC 5 Box Culvert.
- | | | | |
|-------------------|-----------------------------|----|--------|
| 1:2:4 Concrete | 42.03 C Y @ \$16.50 per C Y | \$ | 693.49 |
| Reinforcing Steel | 3440 Lbs. @ .04 Per Lb. | | 137.60 |
| | TOTAL | \$ | 831.09 |
- (5) Bet. Secs. 22-27, T 17 N., R 13 E. Dr. Area 30 A. C = 0.4
3' x 2' x 26' BC 5 Box Culvert.
- | | | | |
|-------------------|----------------------------|----|--------|
| 1:2:4 Concrete | 8.89 C Y @ \$17.00 per C Y | \$ | 151.13 |
| Reinforcing Steel | 759 Lbs. @ \$.04 per Ln. | | 30.36 |
| | TOTAL | \$ | 181.49 |
- (6) Bet. Secs. 22-27, T 17 N., R 13 E. Dr. Area 30 A C = 0.4
3' x 2' x 26' BC 5 Box Culvert
- | | | | |
|-------------------|----------------------------|----|--------|
| 1:2:4 Concrete | 8.89 C Y @ \$17.00 per C Y | \$ | 151.13 |
| Reinforcing Steel | 759 Lbs. @ .04 per Lb. | | 30.36 |
| | Total | \$ | 181.49 |
- (7) Bet. Secs. 23-26, T 17 N., R 13 E. Dr. Area 15 A. C = 0.8
3' x 2' -6" x 27' BC 5 Box Culvert.
- | | | | |
|-------------------|-----------------------------|----|--------|
| 1:2:4 Concrete | 10.30 C Y @ \$17.00 per C Y | \$ | 175.10 |
| Reinforcing Steel | 831 Lbs/ @ .04 Per Lb. | | 33.24 |
| | TOTAL | \$ | 208.34 |
- (8) Bet. Secs. 23-26, T 17 N., R 13 E. Dr. Area 80 A. C = 0.4
6' x 2' x 26' BC 5 Box Culvert.
- | | | | |
|-------------------|-----------------------------|----|--------|
| 1:2:4 Concrete | 15.95 C Y @ \$16.80 per C Y | \$ | 267.96 |
| Reinforcing Steel | 1412 Lbs. @ .04 Per Lb. | | 56.48 |
| | TOTAL | \$ | 324.44 |
- TOTAL FOR DRAINAGE STRUCTURES
IN BIXBY TOWNSHIP. \$ 2,254.93

GLENN POOL TOWNSHIP.

- (1) Bet. Secs. 6-7, T 17 N., R 13 E. Dr. Area 20 A. C = 0.6
3' x 2' x 26' BC 5 Box Culvert
- | | | | |
|-------------------|----------------------------|----|--------|
| 1:2:4 Concrete | 8.89 C Y @ \$17.00 per C Y | \$ | 151.13 |
| Reinforcing Steel | 759 Lbs. @ .04 per Pd | | 30.36 |
| | TOTAL | \$ | 181.49 |