

Bet (4)	Bet. Secs. 25-26, T 22, R 13 3 x 3 x 30' BC 5 Box Culvert	Dr. Area 30 A. Fast Rolling.	
	1:2:4 Concrete	12.33 C Y @ \$19.50 per CY	\$240.44
	Reinforcing Steel	1018 Lbs. @ .05 per Lb.	50.90
		Total	\$291.34
(5)	Bet. Secs. 25-26, T 22, R 13. 4 x 2 x 30' BC 5 Box Culvert	Dr. Area 30 A. Fast Rolling.	
	1:2:4 Concrete	12.27 C Y @ \$19.50 per CY	\$239.26
	Reinforcing Steel	1099 Lbs. @ .05 per Lb.	54.95
		Total	\$293.21
(6)	Bet. Sec. 35-36, T. 22, R 13. Double 4 x 2' 6" x 30' BC Box Culv.	Dr. Area 125 A. Fast Rolling.	
	1:2:4 Concrete	25.69 C Y @ \$19.50 per C Y	\$500.95
	Reinforcing Steel	2166 Lbs. @ .05 per Lb.	108.30
		Total	\$609.25
(7)	Bet. Sec. 35-36, T 22, R 13. 32' of 24" R C L J Pipe Culvert with Headwalls	Dr. A. 10 A. F R. Pipe to be furnished by County at Site of work.	
	Installing 24" R C Pipe 32 L F @	\$11.50 per L F	\$ 48.00
	1:2:4 Concrete	2.24 C Y @ \$19.50 per C Y	\$ 43.68
	Reinforcing Steel 56 Lbs.	@ .05 per lb.	2.80
		Total	\$ 94.48
(8)	Bet. Sec. 35-36, T 22, R 13. 8 x 3 x 30' BC 5 Box Culvert	Drainage Area 170 Acres. Fast Rolling.	
	1:2:4 Concrete 29.09 C Y @ \$19.50 per C Y		\$567.25
	Reinforcing Steel 2620 Lbs. @ .05 per Lb.		\$131.00
		Total	\$698.25
(9)	Bet. Sec. 35-36, T 22, R 13. 4 x 2 x 30' BC 5 Box Culvert	Dr. Area. 40 A. Fast Rolling.	
	1:2:4 Concrete 12.27 C Y @ 19.50 per C Y		\$239.26
	Reinforcing Steel 1099 Lbs. @ \$.05 per Lb.		54.95
		Total	\$294.21
(10)	Bet. Sec. 25, T 22, R 13 & Sec. 30, T 22, R 14. 5 x 3 x 20' BC 5 Box Culvert - with special U Type Wings	Dr. Area 75 A. Light Hilly.	
	1:2:4 Concrete 12.0 C Y @ \$19.50 per C Y		\$234.00
	Reinforcing Steel 1080 Lbs. @ \$.05 per Lb.		54.00
		Total	\$288.00
(11)	Bet. Sec. 25, T 22, R 13 & Sec. 30 T 22, R 14. 2 x 2 x 20' BC Box Culvert-with special U-Type Wings	Dr. Area 15 A., Fast Rolling	
	1:2:4 Concrete 5.50 C Y @	\$19.50 per C Y	\$107.25
	Reinforcing Steel 500 Lbs. @	.05 per Lb.	25.00
		Total	\$132.25
(12)	Bet. Sec. 25, T 22, R 13 & Sec. 30, T 22, R 14. 3 x 2 x 20' BC 5 Box Culvert-with special U-Type Wings	Dr. Area 20 A Fast Rolling	
	1:2:4 Concrete 6.70 C Y @ \$19.50 per CY		\$130.65
	Reinforcing Steel 600 Lbs. @ \$.05 per Lb.		30.00
		Total	\$160.65
(13)	Bet. Sec. 36-31, T 22, R 13-14 3 x 2 x 20' BC 5 Box Culvert-with special U-Type Wings.	Dr. Area 20 A. Fast Rolling.	
	1:2:4 Concrete 6.70 C Y @ \$19.50 per C Y		\$130.65
	Reinforcing Steel 600 Lbs. \$ \$.05 per Lb.		30.00
		Total	\$160.65
(14)	Bet. Sec. 36-31, T 22, R 13-14 5 x 2' 6" x 20' BC 5 Box Culvert with special U type wings.	Dr. Area 70 A. Fast Rolling.	
	1:2:4 Concrete 11.00 C Y @ \$19.50 per C Y		\$214.50
	Reinforcing Steel 1000 Lbs. .05 per Lb.		\$ 50.00
		Total	\$264.50
(15)	Bet. Sec. 36-31, T 22, R 13-14. 3 x 2' 6" x 20' BC 5 Box Culvert-with special U type wings.	Dr. Area 35 A. Fast Rolling.	
	1:2:4 Concrete. 7.40 C Y @ \$19.50 per C Y		\$144.30
	Reinforcing Steel 640 Lbs. @ .05 per Lb.		32.00
		Total	\$176.30
(16)	Bet. Sec. 36-31, T 22, R 13-14. 24' of 18" R C Pipe Culvert with End walls Pipe to be furnished by County at site of work.	Dr. Area 5 A. Fast Rolling	
	Installing 18" R C Pipe 24 L F	@ \$1.00 Per L F	\$ 24.00
	1:2:4 Concrete 1.54 C Y @ \$	19.50 per C Y	30.03
	Reinforcing Steel 28 Lbs. @	.05 per Lb.	1.40
		Total	\$ 55.43