

LYNN LANE TWP.

(1)	Bet. Sec. 17-16, T 19 R 14. Double 5 x 3 x 20' BC 5 A.Box Culvert with "U" Type Wings.	Dr.Area 260 A. Fast Rolling.	
	1:2:4 Concrete	22.80 C Y @ \$18.00 per C Y	\$410.40
	Reinforcing Steel	1930 Lbs. @ .05 per Lb.	96.50
		Total	\$506.90
(2)	Bet. Sec. 16-17, T 19 R 14. 4 x 2 x 20' BC 5 Box Culvert with U type Wings.	Dr.Area 37 A. Fast Rolling.	
	1:2:4 Concrete	8.40 C Y @ \$19.00 per C Y	\$159.60
	Reinforcing Steel	760 Lbs. @ .05 per Lb.	38.00
		Total	\$197.60
(3)	Bet. Sec. 9-16, T 19 R 14. 3 x 2 x 20' BC 5 Box Culvert with U type Wings.	Dr.Area 30 A. Fast Rolling.	
	1:2:4 Concrete	6.70 C Y @ \$19.00 per C Y	\$127.30
	Reinforcing Steel	600 Lbs. @ .05 per Lb.	30.00
		Total	\$157.30
(4)	Bet. Sec. 9-16, T 19 R 14. Double 4 x 2'6" BC 5A Box Culvert with U type wings.	Dr.Area 135 A. Fast Rolling.	
	1:2:4 Concrete	18.80 C Y @ \$19.00 per C Y	\$357.20
	Reinforcing Steel	1540 Lbs. @ .05 Per Lb.	77.00
		Total	\$434.20
(5)	Bet. Sec. 9-16, T 19 R 14. 3 x 3 x 20' BC 5 Box Culvert with U type Wings.	Dr.Area 40 A. Fast Rolling.	
	1:2:4 Concrete	8.00 C Y @ \$19.00 per C Y	\$152.00
	Reinforcing Steel	720 Lbs. @ .05 per Lb.	36.00
		Total	\$188.00
(6)	Bet. Sec. 10-15, T 19, R 14 3 x 2 x 20' BC 5 Box Culvert with U Type Wings.	Dr.Area 20 A. Fast Rolling.	
	1:2:4 Concrete	6.70 C Y @ \$19.00 per C Y	\$127.30
	Reinforcing Steel	600 Lbs. @ .05 per Lb.	30.00
		Total	\$157.30
(7)	Bet. Sec. 10-15, T 19, R 14. 24' of 15" R C Pipe Culvert with endwalls. Pipe to be furnished by County at site of work.		
	Installing 15" R C Pipe 24 L F @ \$1.25 per L F		\$ 30.00
	1:2:4 Concrete 1.08 C Y @ \$19.00 per C Y		20.52
	Reinforcing Steel 26 Lbs. @ \$.05 per Lb.		1.30
		Total	\$ 51.82
(8)	Bet. Sec. 10-15, T 19 R 14. 4 x 2 x 20' BC Box Culvert with U Type Wings.	Dr.Area 40 A. Fast Rolling	
	1:2:4 Concrete	8.40 C Y @ \$19.00 per C Y	\$159.60
	Reinforcing Steel	760 Lbs. @ \$.05 per Lb.	38.00
		Total	\$197.60
(9)	Bet. Sec. 10-15, T 19, R 14. 2 x 2 x 20' BC 5 Box Culvert with U type Wings.	Dr.Area 15 A. Fast Rolling.	
	1:2:4 Concrete	5.50 C Y @ \$20.00 per C Y	\$110.00
	Reinforcing Steel	500 Lbs. @ .05 per Lb.	25.00
		Total	\$135.00
(10)	Bet. Sec. 9010, T 19 R 14. 2 x 2 x 20' BC 5 Box Culvert with U Type Wings.	Dr.Area 15 A. Fast Rolling	
	1:2:4 Concrete	5.50 C Y @ \$20.00 per C Y	\$110.00
	Reinforcing Steel	500 Lbs. @ .05 per Lb.	25.00
		Total	\$135.00
(11)	Bet. Sec. 9-10, T 19 R 14. 4 x 3 x 20' BC 5 Box Culvert with U Type Wings.	Dr.Area 75 A. Fast Rolling.	
	1:2:4 Concrete	10.00 C Y @ \$19.00 per C Y	\$190.00
	Reinforcing Steel	900 Lbs @ \$.05 per Lb.	45.00
		Total	\$235.00
(12)	Bet. Sec. 15-16, T 19 R 14. 3 x 2 x 20' BC 5 Box Culvert with U type Wings.	Dr.Area 20 A. Fast Rolling.	
	1:2:4 Concrete	6.70 C Y @ \$19.00 per C Y	\$127.30
	Reinforcing Steel	600 Lbs. @ \$.05 per Lb.	30.00
		Total	\$157.30
(13)	Bet. Sec. 15-16, T 19, R 14. 4 x 4 x 20' BC 5 Box Culvert with U type wings.	Dr.Area 100 Acres. Fast Rolling.	
	1:2:4 Concrete	13.70 C Y @ \$19.00 per C Y	\$260.30
	Reinforcing Steel	1030 Lbs. @ \$.05 per Lb.	\$ 51.50
		Total	\$311.80