

September 28th. 1925.

The Board of County Commissioners met in their office on Thursday, October 24th. with all members present: J S Shaver, Chairman, W L North and Ed W Hedgecock, Members. O G Weaver, County Clerk.

The matter of awarding contracts for certain improvements on Tulsa County Highways was taken up, the following proposals being submitted and contracts were awarded to cover:

PROPOSAL FOR ERECTION OF CULVERTS.

Limestone School House Road South
of Broken Arrow.
Section "KK"
Tulsa County Highway.

Hon. County Commissioners,
Tulsa County, Oklahoma.

Gentlemen:

The undersigned, being familiar with the location and character of the work to be done and performed; materials to be used and the plans and written directions as set out on the said plans, proposes to furnish all materials and labor and to complete strictly in accordance with the said plans, and Oklahoma Standard Specifications, the hereinafter described culverts and bridges, complete and in place, including all excavation, backfilling, removal of old structures, providing detours for traffic, at the following prices, to-wit:

Limestone School House Road.

Bet. Sec. 26-35, Twp 19 N., R 11 E
8' x 8' x 32' Box Culvert

1:2:4 Concrete	66.0 C.Y.	@ \$19.25 per C Y	\$1,270.50
Reinforcing Bars	3600. Lbs.	@ .06 Per Lb.	216.00
Total			1,486.50

Bet. Sec. 27-34, Twp. 19 N. R 11 E.
9' x 9' x 30' Box Culvert

1:2:4 Concrete	78.0 C Y	@ \$19.25 per C Y	\$1,501.50
Reinforcing Bars	4000 Lbs	@ .06 Per Lb	240.00
Total			1,741.50

Bet. Sec. 27-34 Twp 19 N R 11 E.
16' x 4' x 24' Slab Top Bridge

1:2:3 Concrete	25.0 C Y	@ \$19.50 per C Y	487.50
1:2:4 Concrete	40.0 C Y	@ 19.00 per C Y	760.00
Reinforcing Bars	4000. Lbs	@ .06 per Lb.	240.00
Total			1,487.50

Bet. Sec. 27-28 Twp 19 N. R 11 E
4' x 3' x 30' Box Culvert

1:2:4 Concrete	16.5 C Y	@ \$20.00 Per C Y	330.00
Reinforcing Bars	1400. Lbs.	@ .06 per Lb.	84.00
Total			414.00

Bet. Sec. 22-27, Twp. 19 N., R 11 E.

2' x 3' x 30' Box Culvert

1:2:4 Concrete	11.0 C Y	@ \$20.00 per C Y	220.00
Reinforcing Bars	900. Lbs	@ .06 Per Lb	54.00
Total			274.00

Bet. Sec. 22-27, Twp 19 N. R 11 E.
36' of 24" Concrete Pipe Culvert

37.5' of 24" Conc. Pipe in Place	37.5 L F	@ \$ 4.50 per L F	168.75
1:2:4 Concrete Headwalls	3.0 C Y	@ 23.00 Per C Y	69.00
TOTAL			237.75

Bet. Sec. 22-33 Twp 19 N R 11 E
4' x 4' x 30' Box Culvert

1:2:4 Concrete	21.5 C Y	@ \$19.75 Per C Y	424.62
Reinforcing Bars.	1500. Lbs	@ .06 Per Lb.	90.00
Total			514.62

TOTAL ON LIMESTONE SCHOOL HOUSE ROAD \$6,155.87