

NOTE: The work proposed herein is Township work and will be paid for with Township Warrants.

APPROXIMATE QUANTITIES.

REDFORK TOWNSHIP

- | | | | |
|------|--|-----------------------------|-------------|
| (1) | Between Sections 34-3, T 19-18 N., R 12 E.
3' x 3' x 32' BC 5 | Sta. 5 / 07 61st.Street. | |
| | 1:2:4 Concrete | 12.85 C Y @ \$10.75 Per C Y | \$ 138.14 |
| | Reinforcing Steel | 1070 Lbs @ 2.50 per Lb. | 26.75 |
| | | TOTAL | 164.89 |
| (2) | Between Sections 34-3 T 19-18 N. R 12 E.
44' -24" R C Pipe Culvert.
R C Pipe in Place - Headwalls to be built. | Sta. 11 / 15 61st.Street | |
| | 1:2:4 Concrete | 2.08 C Y @ \$10.75 per C Y | 22.36 |
| | Reinforcing Steel | 56 Lbs @ 2.50 per Lb. | 1.40 |
| | | TOTAL | 23.76 |
| (3) | Between Sections 34-3 T 19-18 N., R 12 E.
8' x 6' x 36' BC 5 | Sta 17 / 30 61st.Street. | |
| | 1:2:4 Concrete | 50.78 C Y @ \$10.75 Per C Y | 545.89 |
| | Reinforcing Steel | 3805 Lbs @ 2.50 per Lb. | 95.13 |
| | | TOTAL | 641.02 |
| (4) | Bet. Sections 34-3, T 19-18 N. R 12 E.
10' x 8' x 39' BC 5 - Special Top, Bottom
and Sides of Box 12" thick. | Sta. 20 / 00 61st.Street. | |
| | 1:2:4 Concrete | 82.40 C Y @ \$10.75 Per C Y | 885.80 |
| | Reinforcing Steel | 5923 Lbs @ 2.50 Per Lb. | 148.08 |
| | | TOTAL | \$ 1,033.88 |
| (5) | Bet. Sections 34-3 T 19-18 N., R 12 E
8' x 5' x 30' BC 5 | Sta 24 / 15 61st.Street. | |
| | 1:2:4 Concrete | 39.13 C Y @ \$10.75 per C Y | 420.65 |
| | Reinforcing Steel | 3063 Lbs @ 2.50 Per Lb. | 76.58 |
| | | TOTAL | \$ 497.23 |
| (6) | Bet. Sections 34-3, T 19-18 N., R 12 E.
4' x 4' x 54' BC 6 - Skewed 45° | Sta. 29 / 30 61st.Street. | |
| | 1:2:4 Concrete | 31.70 C Y @ \$10.75 Per C Y | 340.78 |
| | Reinforcing Steel | 2460 Lbs. @ 2.50 Per Lb. | 61.50 |
| | | TOTAL | \$ 402.28 |
| (7) | Bet. Sections 33-4, T 19-18 N., R 12 E.
6' x 3' x 30' BC 5 | Sta. 53 / 95 61st.Street | |
| | 1:2:4 Concrete | 22.20 C Y @ \$10.75 per C Y | 238.65 |
| | Reinforcing Steel | 1810 Lbs @ 2.50 per Lb. | 45.25 |
| | | TOTAL | 283.90 |
| (8) | Bet. Sections 33-4, T 19-18 N., R 12 E.
5' x 3' x 30' BC 5 | Sta 65 / 85 61st.Street | |
| | 1:2:4 Concrete | 17.25 C Y @ \$10.75 Per C Y | 185.44 |
| | Reinforcing Steel | 1498 Lbs @ 2.50 Per Lb. | 37.45 |
| | | TOTAL | 222.89 |
| (9) | Bet. Sections 33-4, T 19-18 N., R 12 E.
8' x 3' x 32' BC 5 | Sta. 78 / 00 61st.Street. | |
| | 1:2:4 Concrete | 30.54 C Y @ \$10.75 Per C Y | 328.31 |
| | Reinforcing Steel | 2768 Lbs. @ 2.50 per Lb. | 69.20 |
| | | TOTAL | 397.51 |
| (10) | Bet. Sections 33-4, T 19-18 N., R 12 E.
33' -18" R C Pipe Culvert.
R C Pipe in place - Headwalls to be built. | Sta. 86 / 30 61st.Street. | |
| | 1:2:4 Concrete | 1.47 C Y @ \$10.75 Per C Y | 15.80 |
| | Reinforcing Steel | 28 Lbs @ 2.50 Per Lb. | .70 |
| | | TOTAL | \$ 16.50 |
| (11) | Bet. Sections 33-4, T 19-18 N., R 12 E.
32' -24" R C Pipe Culvert
R C Pipe in place - Headwalls to be built. | Sta. 99 / 08 61st.Street | |
| | 1:2:4 Concrete | 2.08 C Y @ \$10.75 Per C Y | 22.36 |
| | Reinforcing Steel | 56 Lbs @ 2.50 Per Lb. | 1.40 |
| | | TOTAL | \$ 23.76 |
| (12) | Bet Sections 33-4, T 19-18 N., R 12 E.
36' -30" R C Pipe Culvert.
R C Pipe in place - Headwalls to be built. | Sta 102 / 00 61st.Street | |
| | 1:2:4 Concrete | 2.77 C Y @ \$10.75 per C Y | 29.78 |
| | Reinforcing Steel | 62 Lbs @ 2.50 per Lb. | 1.55 |
| | | TOTAL | 31.33 |