

(6)	In Section 14, T 20 N., R 12 E. 2' x 2' x 52' BC 6 Box Culvert. 1:2:4 Concrete Reinforcing Steel	Sta. 84 / 75 12.37 C Y @ \$18.00 per C Y 1152. Lbs. @ .04 Per Lb.	\$ 222.66 46.08 Total \$ 268.74
(7)	In Section 14, T 20 N., R 12 E. 2' x 2' x 80' BC 6 Skewed. 1:2:4 Concrete Reinforcing Steel	Sta. 88 / 20 Dr. Area 8 A. C = 1.0 17.55 C Y @ \$18.00 per C Y 1694 Lbs. @ .04 per Lb.	\$ 315.90 67.76 Total \$ 383.66
(8)	In Section 14, T 20 N., R 12 E. 2' 2' 2' x 36' BC 5 Box Culvert. 1:2:4 Concrete Reinforcing Steel	Sta. 91 / 50 Dr. Area 4 A. C = 1.0 9.41 C Y @ \$18.00 per C Y 843 Lbs. @ .04 Per Lb.	\$ 169.38 33.72 Total 203.10
(9)	In Section 14, T 20 N., R 12 E. 43' x 15' x 24' I BM Concrete Bridge. Over Flat Rock Creek. ABUTMENTS: 1:2:4 Concrete Reinforcing Steel	Sta. 93 / 05 216.28 C Y @ \$18.00 per C Y 20,210 Lbs. @ .04 Per Lb.	\$ 3,893.04 808.40
	FLOOR SYSTEM: 1:2:3 Concrete Reinforcing Steel Structl. Stl. I-Bms. 28"-97 Lbs. Structural Steel, Miscellaneous Hand Rail Complete Floor Drains, Iron Pipe 2 1/2" Diam.	36.62 C Y : \$18.00 per C Y 4210 Lbs. @ \$.04 26,578 Lbs. @ \$.05 per Lb. 2,418 Lbs. @ \$.05 Per Lb. 96 L F @ \$ 2.00 per L F 11 L F @ \$1.00 per L F	\$ 659.16 168.40 1,328.90 120.90 192.00 11.00 Total \$ 7,181.80
(10)	In Section 14, T 20 N., R 12 E. 2' x 2' x 38' BC 5 Box Culvert. 1:2:4 Concrete Reinforcing Steel	Sta. 100 / 40 Dr. Area 10 A C = 0.5A 9.78 C Y @ \$18.00 per C Y 882 Lbs. @ \$.04 Per Lb.	\$ 176.04 35.28 Total \$ 211.32
(11)	Bet Secs. 13-14, T 20 N., R 12 E. 36' -18" R C Pipe Culvert. County will furnish pipe at site of work. Installing 18" R C Pipe 1:2:4 Concrete Reinforcing Steel	Sta. 108 / 50 Dr. Area 3 A C = 0.5 36 L F @ \$11.00 Per L F 1.47 C Y @ \$18.00 per C Y 28 Lbs. @ .04 Per Lb.	\$ 36.00 26.46 1.12 Total \$ 63.58
(12)	Bet. Secs. 13-14, T 20 N., R 12 E. 2' x 2' x 32' BC 5 Box Culvert 1:2:4 Concrete Reinforcing Steel	Sta. 111 / 75 Dr. Area 15 A. C = 0.5 8.67 C Y @ \$18.00 per C Y 766 Lbs. @ .04 Per Lb.	\$ 156.06 30.64 Total \$ 186.70
(13)	Bet. Secs. 11-12, T 20 N., R 12 E. 5' x 2'-6" x 32' BC 5 Box Culvert. 1:2:4 Concrete Reinforcing Steel	Sta. Dr. Area 60 A C = 0.5 16.64 C Y @ \$18.00 per C Y 1489 Lbs. @ .04 Per Lb.	\$ 299.52 59.56 Total \$ 359.08
(14)	Bet. Secs. 11-12, T 20 N., R 12 E. Double 6' x 3' x 32' BC 5 A Box Culvert. 1:2:4 Concrete Reinforcing Steel	Sta. Dr. Area 300 A. C = 0.5 42.67 C Y @ \$18.00 per C Y 3612 Lbs. @ .04 Per Lb.	\$ 768.06 144.48 Total \$ 912.54
(15)	Bet. Secs. 11-12, T 20 N., R 12 E. 32' -18" R C Pipe Culvert. County will furnish pipe at site of work. Installing 18" R C Pipe 1:2:4 Concrete Reinforcing Steel	Sta. Dr. Area 3 A C = 0.7 32 L F @ \$1.00 per L F 1.47 C Y @ \$18.00 per C Y 28 Lbs. @ \$.04 per Lb.	\$ 32.00 26.46 1.12 Total \$ 59.58
(16)	Bet. Secs. 1-2, T 20 N., R 12 E. 10' x 6' x 32' BC 5 Box Culvert. 1:2:4 Concrete Reinforcing Steel	Dr. Area 500 A C = 0.5 54.78 C Y @ \$18.00 per C Y 4318 Lbs. @ .04 Per Lb.	\$ 986.04 172.72 Total \$ 1,158.76

GRAND TOTAL \$12,127.92

Force Account, or Extra work, only when ordered in writing by the County Engineer at ACTUAL COST, Plus Fifteen (15%) Per Cent.

If awarded, the said work, we propose to immediately enter into contract, furnishing acceptable Surety Company Bonds, both Contract and Statutory in the full amount of the contract price, agreeing to begin the said work within Ten (10) days after work order is issued by the County Engineer, and to complete the same to your acceptance within Sixty (60) ~~days~~ working days after receiving said work order.

Upon failure to complete within the time limit as proposed, we agree to all the provisions embodied in the Oklahoma State Standard Specifications respecting failure to complete within the specified time as bid.

When mutually agreed to by and between your Honorable Board and ourselves, this proposal may be considered for extension to additional work of the same character and upon