

APPROXIMATE QUANTITIES

PAVING:

4,300 Lin.Ft.of 18 feet wide,
9"-6" -9" thick, 1:2:3½ Mixture
Tulsa County Portland Cement Reinforced
Concrete Paving iwht Curves, including
all reinforcing, Metal Center Strips and
Pins, Asphalt Joints, etc. Complete as per
attached plan and Section.
Coarse Aggregate for concrete to be
Crushed Limestone.

Approx. 8,760 Sq.Yds. @\$1.82 per Sq.Yd. \$ 15,943.20

FINE GRADING:

Grading to Subgrade, Shaping and
Rolling the same and Construction of
shoulders after completion of Paving,
Cleaning out Side Ditches, etc. To
be paid for according to the number
of Square Yards of Paving laid. All
payment for Grading to be covered by
the price of Fine Grading.

Approx. 8,760 Sq.Yds @\$.10 Per Sq.Yd. 876.00

LIP CURB

Approx. 2,000 Lin.Ft. @\$.10 per Lin Ft. 200.00

TOTAL JOB #1. \$ 17,019.20

PROPOSAL NO. TWO.

PROPOSAL FOR PAVING AND OTHERWISE
IMPROVING THE SOUTH THREE THOUSAND
FIVE HUNDRED FORTY FIVE (3,545') LIN.
FEET ON THIRTY THIRD WEST AVE. BETWEEN
SECTIONS 33-34, T 19 N., R 12 E.

IN RED FORK TOWNSHIP.

APPROXIMATE QUANTITIES

PAVING:

3,545 Lin.Feet of 18 feet wide,
9"-6" -9" thick, 1:2:3½ Mixture
Tulsa County Portland Cement
Reinforced Concrete Paving, including
all Reinforcing, Metal Strips and Pins
Asphalt Joints, etc. Complete as per
attached Plan and Section. Coarse
Aggregate for concrete to be Crushed
Limestone.

Approx. 7,090 S q.Yds. @ \$1.82 per Sq.Yd. \$ 12,903.80

FINE GRADING:

Grading to Subgrade, shaping and
Rolling the same and Construction
of shoulders after completion of
Paving, Cleaning out Side Ditches
etc/. To be paid for according to
the number of Square Yards of Paving
laid. All Payment for Grading to be
covered by the price for Fine Grading.

Approx. 7,090 Sq.Yds @\$.10 per Sq.Yd 709.00

LIP CURB:

Approx. 3,600 Lin.Ft. @ \$0.10 Per Lin Ft. 360.00

TOTAL JOB #2. \$ 13,972.80

TOTAL JOB NO.1 AND JOB NO. 2 \$ 30,992.00

Force Account, or Extra Work, only when ordered
in writing by the County Engineer, at ACTUAL COST
Plus Fifteen (15%) Per Cent.

If awarded the said work, we propose to immediately enter into contract,
furnishing acceptable Surety Company Bonds, both Contract and Statutory, in the full
amount of the Contract Price, agreeing to begin the said work immediately after WORK ORDER
is issued by the County Engineer, and to complete the same to your acceptance
within Ten (10) WORKING DAYS after WORK ORDER is issued by the County Engineer. Upon
failure to complete within the time limit as proposed, we agree to all the provisions
embodied in the Oklahoma State Standard Specifications respecting failure to complete
within the specified time as bid.