

REDFORK TOWNSHIP.

ON 51ST. STREET.

- (1) Between Sections 30-31, T 19 N., R 12 E. Sta. 78 / 70
 24' - 30" R C Pipe Culvert Dr. Area 12 A. C = 0.5
 Extend 16' to 40' - 30" R C Pipe Culvert
 Tulsa County will deliver pipe at site of work.
- | | | |
|-------------------------|----------------------------|----------|
| Installing 30" R C Pipe | 16 L F @ \$.90 Per L F | \$ 14.40 |
| 1:2:4 Concrete | 2.77 C Y @ \$12.00 per C Y | 33.24 |
| Reinforcing Steel | 62 Lbs. @ .024 per Lb. | 1.48 |
| TOTAL | | \$ 49.12 |
- (2) Between Sections 30-31, T 19 N., R 12 E. Sta. 81 / 65
 24' - 18" R C Pipe Culvert Dr. Area 4 A. C = 0.5
 Remove to Sta. 81 / 35 and Extend 21 Feet to 45' - 18" R C Pipe Culvert
 Tulsa County will deliver pipe at site of work.
- | | | |
|-----------------------------------|------------------------------|----------|
| Installing 18" R C Pipe | 45 L F @ \$.65 per L F | \$ 29.25 |
| 1:2:4 Concrete | 1.47 Per C Y \$12.00 per C Y | 17.64 |
| Reinforcing Steel | 28 Lbs. @ .024 Per Lb. | .67 |
| Removing 18" Pipe to new location | 24 L F @ \$.65 Per L F. | 15.60 |
| TOTAL | | \$ 63.16 |
- (3) In Section 31, T 19 N., R 12 E. Sta. 86 / 25
 3' x 2' - 6" x 40' BC 5 Culvert Dr. Area 20 A C = 0.8
- | | | |
|-------------------|----------------------------|-----------|
| 1:2:4 Concrete | 13.43 C Y @ \$9.60 per C Y | \$ 128.92 |
| Reinforcing Steel | 1141 Lbs. @ .024 Per Lb. | 27.38 |
| TOTAL | | 156.30 |
- (4) In Section 31, T 19 N., R 12 E. Sta. 90 / 40
 2' x 2' x 40' BC 5 Culvert - No culvert in place. Dr. Area 8 A. C = 0.8
- | | | |
|-------------------|-----------------------------|-----------|
| 1:2:4 Concrete | 10.15 C Y @ \$10.00 Per C Y | \$ 101.50 |
| Reinforcing Steel | 920 Lbs. @ .024 per Lb. | 22.08 |
| TOTAL | | 123.58 |
- (5) In Section 31, T 19 N., R 12 E. Sta. 94 / 45
 2' x 2' x 42' BC 5 Culvert - No culvert in place. Dr. Area 4 A. C = 1.0
- | | | |
|-------------------|-----------------------------|-----------|
| 1:2:4 Concrete | 10.52 C Y @ \$10.00 per C Y | \$ 105.20 |
| Reinforcing Steel | 959 Lbs. @ .024 Per Lb. | 23.01 |
| TOTAL | | \$ 128.21 |
- (6) In Section 31, T 19 N., R 12 E. Sta. 97 / 40
 2' x 2' x 40' BC 5 Culvert - No culvert in place. Dr. Area 4 A. C = 1.0
- | | | |
|-------------------|-----------------------------|-----------|
| 1:2:4 Concrete | 10.15 C Y @ \$10.00 per C Y | \$ 101.50 |
| Reinforcing Steel | 920 Lbs. @ .024 Per Lb. | 22.08 |
| TOTAL | | \$ 123.58 |
- (7) In Section 31, T 19 N., R 12 E. Sta. 101 / 40
 2' x 2' x 35' BC 5 Culvert - No culvert in place. Dr. Area 3 A. C = 1.0
- | | | |
|-------------------|----------------------------|----------|
| 1:2:4 Concrete | 9.23 C Y @ \$10.00 Per C Y | \$ 92.30 |
| Reinforcing Steel | 824 Lbs. @ .024 Per Lb. | 19.77 |
| TOTAL | | 112.07 |
- (8) In Section 31, T 19 N., R 12 E. Sta. 104 / 75
 3' x 2' - 6" x 36' BC 5 Culv. No. Culvert in place. - Dr. Area 12 A. C = 1.0
- | | | |
|--------------------|----------------------------|-----------|
| 1:2:4 Concrete | 12.47 C Y @ \$9.75 Per C Y | 121.58 |
| Reinforcing Steele | 1045 Lbs. @ .024 Per Lb. | 25.08 |
| TOTAL | | \$ 146.66 |
- (9) In Section 31, T 19 N., R 12 E. Sta. 119 / 55
 3' x 2' x 38' BC 5 Culvert - No culvert in place Dr. Area 10 A C = 1.0
- | | | |
|-------------------|----------------------------|-----------|
| 1:2:4 Concrete | 11.56 C Y @ \$9.75 Per C Y | \$ 112.71 |
| Reinforcing Steel | 1035 Lbs. @ .024 Per Lb. | 24.84 |
| TOTAL | | \$ 137.55 |
- (10) In Section 31, T 19 N., R 12 E. Sta. 112 / 89
 2' x 2' x 37' BC 5 Culvert - No culvert in place. - Dr. Area 6 A. C = 1.0
- | | | |
|-------------------|----------------------------|-----------|
| 1:2:4 Concrete | 9.60 C Y @ \$10.00 per C Y | \$ 96.00 |
| Reinforcing Steel | 863 Lbs. @ .024 Per Lb. | 20.71 |
| TOTAL | | \$ 116.71 |
- (11) In Section 31, T 19 N., R 12 E. Sta. 114 / 75
 3' x 2' x 40' BC 5 Culvert - No culvert in place. Dr. Area 8 A. C = 1.0
- | | | |
|-------------------|----------------------------|--------|
| 1:2:4 Concrete | 12.00 C Y @ \$9.75 Per C Y | 117.00 |
| Reinforcing Steel | 1081 Lbs. @ .024 per Lb. | 25.94 |
| TOTAL | | 142.94 |
- (12) In Section 30 T 19 N., R 12 E. Sta. 120 / 10
 3' x 2' x 58' BC 6 Culvert - Make top of Culvert 7" thick.
 No Culvert in place. Dr. Area 10 A C = 1.0
- | | | |
|-------------------|----------------------------|--------|
| 1:2:4 Concrete | 16.74 C Y @ \$9.75 Per C Y | 163.21 |
| Reinforcing Steel | 1495 Lbs. @ .024 Per Lb. | 35.88 |
| Total | | 199.09 |