

(13)	In Section 30, T 19 N., R 12 E. 2' x 2' x 34' BC 5 Culvert - Special End.	Sta. 123 + 22 Dr. Area 4 A. C = 1.0
	1:2:4 Concrete Reinforcing Steel	9.04 C Y @ \$10.00 Per C Y 804 Lbs. @ .024 Per Lb.
		\$ 90.40 19.29 TOTAL \$ 109.69
(14)	In Section 30, T 19 N., R 12 E. 3' x 2' x 66' BC 6 Culvert - No Culvert in place Make top of culvert 7" thick	Sta. 125 + 85 Dr. Area 7 A. C = 1.0
	1:2:4 Concrete Reinforcing Steel	18.61 C Y @ \$9.75 per C Y 1679 Lbs. @ .024 Per Lb.
		181.44 40.29 TOTAL \$ 221.73
(15)	On N & S Center Line of Sec. 27, T 19 N., R 12 E. Double 10' x 10' x 38' BC 5 A Culvert - Special - Top 13" Thick	SOUTH 25TH. S. Ave. Dr. Area
	1:2:4 Concrete Reinforcing Steel	153.33 C Y @ \$9.70 Per C Y 11,424 Lbs. @ .024 Per Lb.
		\$ 1,487.30 274.17
NOTE: - The cost of removing the bridge now in place to be absorbed in the price bid for concrete. The I-Beams taken out to be neatly piled on the side of the road for County Use.		
	TOTAL	\$ 1,761.47
	TOTAL REDFORK TOWNSHIP	\$ 3,591.86

FRYE TOWNSHIP.

(1)	Bet. Secs. 32-5, T 19-18 N., R 13 E. 5' x 2' -6" x 30' BC 5 Culvert	E. 61st. Street. Dr. Area 60 A. C = 0.6
	1:2:4 Concrete Reinforcing Steel	15.90 C Y @ \$10.00 per C Y 1411 Lbs. @ .024 Per Lb.
		\$ 159.00 33.86 TOTAL \$ 192.86
(2)	Bet. Secs. 4-9, T 18 N., R 13 E. 12' x 6' x 19'-6" Box Culvert Extend on Right 12' x 9' x 8' -3"	E 71st. St. Sta 61 + 65
	1:2:4 Concrete Reinforcing Steel	32.91 C Y @ \$10.00 per C Y 2287 Lbs. @ .024 Per Lb.
		\$ 329.10 54.88 TOTAL \$ 383.98
(3)	Bet. Secs. 4-9, T 18 N., R 13 E. 3' x 3' x 30' Box Culvert - Undermined at lower end - Left. Build apron on lower end.	E 71st. St. Sta. 88 + 30
	1:2:4 Concrete Reinforcing Steel	5.82 C Y @ \$11.00 per C Y 239 Lbs. @ .024 Per Lb.
		\$ 64.02 5.73 TOTAL 69.75
(4)	Bet. Secs. 9-10, T 18 N., R 13 E. 3' x 3' x 45' BC 6 Culvert - No culvert in place.	S. Yale Ave. Sta 2 + 75 Dr. Area 20 A. C = 0.9
	1:2:4 Concrete Reinforcing Steel	16.22 C Y @ \$10.00 per C Y 1411 Lbs. @ .024 Per Lb.
		\$ 162.20 33.86 TOTAL \$ 196.06
(5)	Bet. Secs. 9-10, T 18 N., R 13 E. 5' x 6' x 54' BC 6 Culvert - Special Make top of culvert 9" thick. Transverse Reinf. Top & Bottom 5/8" ϕ Vertical Reinf. on Sides 1/2" ϕ 7" C.C.	S. Yale Ave. Sta 11 + 50 Dr. Area 70 A C = 0.9 7" C.C.
	1:2:4 Concrete Reinforcing Steel	52.56 C Y @ \$10.00 per C Y 3725 Lbs. @ .024 Per Lb.
		\$ 525.60 89.40 TOTAL \$ 615.00
(6)	Bet. Secs. 9-10, T 18 N., R 13 E. 2' x 2' x 28' BC 6 Culvert - No culvert in place.	S. Yale Sta. 20 + 90 Dr. Area 5 A. C = 0.9
	1:2:4 Concrete Reinforcing Steel	11.63 C Y @ \$10.00 Per C Y 1075 Lbs. @ .024 Per Lb.
		116.30 25.80 TOTAL \$ 142.10
(7)	Bet. Secs. 9-10, T 18 N., R 13 E. 4' x 4' x 40' BC 6 Culvert - No culvert in place.	S. Yale Ave. Sta. 28 + 20 Dr. Area 50 A C = 0.9
	1:2:4 Concrete Reinforcing Steel	24.05 C Y @ \$10.00 Per C Y 1819 Lbs. @ .024 Per Lb.
		\$ 240.50 43.65 TOTAL 284.15
(8)	Bet. Secs. 9-10, T 18 N., R 13 E. 8' x 6' x 30' BC 5 Culvert - No culvert in place -	S. Yale Ave. Sta. 51 + 90 Dr. Area 185 A. C = 0.7
	1:2:4 Concrete Reinforcing Steel	44.98 C Y @ \$10.00 Per C Y 3300 Lbs. @ .024 Per Lb.
		\$ 449.80 79.20 TOTAL 529.00
	TOTAL FRYE TOWNSHIP	\$ 2,412.90