

BOLES TOWNSHIP.

(1)	Bet. Secs. 33-4, T 19-18N., R 14 E. Double 8' x 4' x 26' BC 5 A Culvert	Dr. Area 500 A. C = 0.6	
	1:2:4 Concrete	54.00 C Y @ \$10.00 Per C Y	\$ 540.00
	Reinforcing Steel	4629 Lbs. @ .024 Per Lb.	111.09
		TOTAL	651.09
(2)	Bet. Secs. 14-15, T 18 N., R 14 E. Double 8' x 5' x 26' BC 5 A Culvert - Located where stream crosses Sec. line. Old structure in place to be removed.	Dr. Area 750 A . C = 0.6	
	1:2:4 Concrete	61.60 C Y @ \$10.00 Per C Y.	\$ 616.00
	Reinforcing Steel	5003 Lbs. @ .024 Per Lb.	120.07
		TOTAL	736.07
		TOTAL BOLES TOWNSHIP	\$ 1,387.16
		TOTAL PROPOSAL NO. 2. -----	\$11,604.49
		TOTAL PROPOSAL NO.2. USING ALTERNATE STRUCTURE OVER EUCHEE CREEK.-----	\$10,905.51

Force Account, or Extra Work, only when ordered in writing by the County Engineer, at ACTUAL COST, Plus Ten (10%) Per Cent.

NOTE:- It is understood that the approximate quantities herein given may be increased or diminished by the County Engineer, in which case the Unit Prices in this proposal will prevail for such increased or diminished quantities.

If awarded the said work, we propose to immediately enter into contract, furnishing acceptable Surety Company Bonds, both Contract and Statutory, in the full amount of the Contract price. The undersigned agrees to begin the said work within Ten (10) days after WORK ORDER is issued by the County Engineer, and further agrees that the work shall progress at an average rate of not less than TEN CUBIC YARDS (10 C.Y.) of Concrete per day every working day thereafter until the final completion of the work ordered in this Proposal. Upon failure to complete within the time limit as proposed, we agree to all the provisions embodied in the Oklahoma State Standard Specifications respecting failure to complete within the specified time as bid.

Certified Bidder's Bond amounting to \$1,000.00 being approximately 5% of the sum bid and conforming to the "Notice to Contractors" and Oklahoma Statutes, 1933, is hereto attached.

NOTE:- Attention is called to the provision embodied in the published "Notice to Contractors" that proposals must be on forms prepared by the County Engineer.

Respectfully Submitted this 22nd. day of May, 1933.

Address: Keystone, Oklahoma.
Box #4.

M A ROOP, Contractor.

PROPOSAL FOR PARTIAL GRADING OF
WEST FIFTY- FIRST ST.

PROPOSAL NO. 3.
Letting May 22, 1933.

Honorable Board of County Commissioners,
Tulsa County Oklahoma.

Gentlemen:

The undersigned, having examined the location and character of the work to be done and performed in the GRADING of the hereinabove described highway, and being familiar with the OKLAHOMA STATE STANDARD SPECIFICATIONS, Revised July 1, 1932, respecting the construction of highways by bringing to Profile Grade, hereby proposes to furnish labor, materials and equipment and to do the said work in each and every particular according to the stakes, cross-sections, instructions and directions of the County Engineer or his duly authorized assistants, and to complete the same to the final acceptance of the County Engineer and your Honorable Board at the prices hereinafter bid, which prices include all clearing and grubbing; the same being absorbed in the price per cubic yard. The price bid is based on the approximate estimate of quantities which is made for estimating purposes only; payment to be made on the actual quantities moved, at the following unit item prices.

All work specified in this Proposal is an encumbrance against the COUNTY HIGHWAY FUND. It is hereby specifically understood by the undersigned Contractor that WORK ORDER covering work herein bid upon will be issued only when funds are available to pay for same. It is, therefore, understood that if funds are not collected by the County Treasurer to pay the cost of said work herein bid upon, the contract will become void.

BE IT FURTHER UNDERSTOOD between the Contractor and the Board of County Commissioners that WORK ORDER will be issued as soon after July 1, 1933 as final auditing of Funds is made by the County Treasurer and final income credited to the 1932-1933 County Highway Fund.

	APPROXIMATE QUANTITIES.	
Earth Excavation	2,200 C Y @ \$.16 Per C Y	\$ 352.00