

LYNN LANE TOWNSHIP

(1)	Bet.Secs. 11-14, T 19 N., R 13 E., 4' x 2' x 30' BC 5 Box Culvert. 1:2:4 Concrete Reinforcing Steel	Dr.Area 30 A. C = 0.5 12.27 C Y @ \$15.50 per C Y 1099 Lbs. @ 3.4 per Lb.	190.19 37.37 Total 227.56
(2)	Bet.Secs. 11-14, T 19 N., R 13 E. 4' x 2' x 30' BC 5 Box Culvert. 1:2:4 Concrete Reinforcing Steel	Dr.Area 30 A. C = 0.5 12.27 C Y @ \$15.50 per C Y 1099 Lbs. @ 3.4 Per Lb.	190.19 37.37 Total 227.56
(3)	Bet.Secs. 11-14, T 19 N., R 13 E. 3' x 2' x 30' BC 5 Box Culvert. 1:2:4 Concrete Reinforcing Steel	Dr.Area 25 A C = 0.5 9.78 C Y @ \$15.50 per C Y 851 Lbs @ 3.4 per Lb.	151.59 m28.93 Total 180.52
(4)	Bet.Secs. 11-14, T 19 N., R 13 E. 2' x 2' x 30' BC 5 Box Culvert 1:2:4 Concrete Reinforcing Steel	Dr.Area 20 A C = 0.5 8.30 C Y @ \$15.50 per C Y 727 Lbs @ 3.4 per Lb.	128.65 24.72 Total 153.37
(5)	Bet.Secs. 34-35, T 19 N., R 13 E. 4' x 2' x 26' BC 5 Box Culvert. 1:2:4 Concrete Reinforcing Steel	Dr.Area. 20 A C = 0.7 11.11 C Y @ \$15.50 per C Y 977 Lbs. @ \$. 3.4 per Lb.	172.21 33.22 Total 205.43
(6)	Bet.Secs. 34-35, T 19 N., R 13 E. 5' x 2'-6" x 26' BC 5 Box Culvert. 1:2:4 Concrete Reinforcing Steel	Dr.Area 40 A. C = 0.7 14.42 C Y @ \$15.50 per CY 1256 Lbs. @ 3.4 Per Lb.	223.51 42.70 Total 266.21
(7)	Bet.Secs. 34-35, T 19 N., R 13 E. Double 8' x 4' x 26' BC 5A Box Culvert. 1:2:4 Concrete Reinforcing Steel	Dr.Area 400 A. C = 0.7 54.00 C Y @ \$15.50 per C Y 4629 Lbs. @ 3.4 per Lb.	837.00 157.39 Total 994.39
(8)	Bet.Secs. 7-18, T 19 N., R 14 E. 3' x 2'-6" x 30' BC 6 Box Culvert. 1:2:4 Concrete Reinforcing Steel	Dr.Area 86 A C = 0.5 11.02 C Y @ \$15.50 Per C Y 902 Lbs. 3.4 per Lb.	\$170.81 30.67 Total 201.48
(9)	Bet.Secs. 7-18, T 19 N., R 14 E. 8' x 2' -6" x 30' BC 5 Box Culvert. 1:2:4 Concrete Reinforcing Steel	Dr.Areal20 A. C = 0.5 27.32 C Y @ \$15.50 per C Y 2538 Lbs. @ 3.4 Per Pb.	423.46 86.29 Total 509.75
(10)	Bet.Secs. 7-18, T 19 N., R 14 E. 32' - 24" R C Pipe Culvert. County will furnish pipe at site of work. Installing 24" R C Pipe 1:2:4 Concrete Reinforcing Steel	Dr.Area. 10 A. c = 0.5 32 L F @ \$1.50 per L F 2.08 C Y @ \$15.50 Per C Y 56 Lbs @ 3.4 Per Lb.	48.00 32.24 1.90 Total 82.14
(11)	Bet.Secs. 11-14, T 19 N., R 14 E. 8' x 4' x 30' BC 5 Box Culvert. 1:2:4 Concrete Reinforcing Steel	Dr.Area 170 A C = 0.6 32.64 C Y @ \$15.50 per C Y 2784 Lbs. @ 3.4 per Lb.	505.92 94.66 Total 600.58
(12)	Bet.S ecs. 11-14 T 19 N., R 14 E. 8' x 6' x 30' BC 5 Box Culvert. 1:2:4 Concrete Reinforcing Steel	Dr.Area 300 A C = 0.6 44.98 C Y @ \$15.50 Per C Y 3300 Lbs. @ 3.4 Per Lb/	697.19 112.20 Total 809.39
(13)	Bet.Secs. 32-5, T 19 - 18 - 14 R.E. 4' x 2' x 46' BC 5 Box Culvert. 1:2:4 Concrete Reinforcing Steel	Dr.Area 35 A. C = 0.6 16.91 C Y @ \$15.50 per C Y 1585 Lbs. @ \$ 3.4 Per Lb.	262.11 53.89 Total 316.00
(14)	Bet.Secs. 32-33 T 19 N., R 14 E. 32' -24" R C Pipe Culvert. County W, ll furnish pipe at site of work. Installing 24" R C Pipe 32 L F @ \$1.50 per L F. 1:2:4 Concrete Reinforcing Steel	Dr.Area 6 A C = 32 L F @ \$1.50 per L F 2.08 C Y @ \$15.50 per C Y 56 Lbs. @ 3.4 Per Lb.	48.00 32.24 1.90 Total \$ 82.14
GRAND TOTAL DOR DRAINAGE STRUCTURES IN LYNN LANE TOWNSHIP			\$4,856.52