

(4)	In Sec. 28, T 22 N., R 14 E. 30' -18" R C Pipe Culvert County will furnish pipe at site of work. Installing 18" R C Pipe 1:2:4 Concrete Reinforcing Steel	Sta. 44 1/2 Dr. Area 5 A C = 0.5 30 L F @ \$1.50 per L F 1.47 C Y @ \$16.25 per C Y 28 Lbs @ \$.038 Per Lb.	\$ 45.00 23.89 1.06 Total 69.95
-----	--	--	---

NOTE: "It is specifically understood and agreed by the undersigned that the above listed drainage structures in Section 28, T 22 N. R 14 E. will not be constructed or paid for unless Tulsa County is able to secure the necessary right of way for highway purposes by amicable settlement".

(5)	Bet. Secs. 28-33, T 22 N., R 14 E. 4' x 2' -6" x 26' BC 5 Box Culvert 1:2:4 Concrete Reinforcing Steel	Dr. Area 40 A C = 0.5 12.30 C Y : \$ 16.25 Per C Y 1025 Lbs. @ \$.038 per Lb.	\$ 199.88 38.95 Total 238.83
-----	---	--	---------------------------------------

(6)	Bet. Secs. 28-33, T 22 N., R 14 E. 2' x 2' x 26' BC 5 Box Culvert 1:2:4 Concrete Reinforcing Steel	Dr. Area 15 A. C = 0.5 7.56 C Y @ \$16.25 per C Y 650 Lbs. @ \$.038 per Lb.	\$ 122.85 24.70 Total 147.50
-----	---	--	---------------------------------------

(7)	Bet. Secs. 28-33 T 22 N., R 14 E. 3' x 2' x 26' BC 5 Box Culvert 1:2:4 Concrete Reinforcing Steel	Dr. Area 20 A C = 0.6 8.89 C Y @ \$16.25 Per C Y 759 Lbs. @ \$.038 Per Lb.	\$ 144.46 28.84 Total 173.30
-----	--	---	---------------------------------------

GRAND TOTAL FOR DRAINAGE STRUCTURES
IN COLLINSVILLE TOWNSHIP \$1,284.53

DAWSON TOWNSHIP

(1)	Bet. Secs. 7 -8 T 20 N., R 14 E. 4' x 4' x 35' BC 5 Box Culvert 1:2:4 Concrete Reinforcing Steel	Dr. Area 75 A C = 0.6 21.91 C Y @ \$14.50 per C Y 1636 Lbs. @ \$.038 Per Lb.	\$ 317.69 62.17 Total \$ 379.86
-----	---	---	--

(2)	Bet Secs. 7-8 T 20 N., R 14 E. 4' x 2' x 26' BC 5 Box Culvert 1:2:4 Concrete Reinforcing Steel	Dr. Area 35 A. C = 0.5 11.11 C Y @ \$14.50 per C Y 977 Lbs. @ \$.038	\$ 161.10 37.13 Total 198.23
-----	---	---	---------------------------------------

(3)	Bet. Secs 7-8, T 20 N., R 14 E. 4' x 2' x 26' NC 5 Box Culvert 1:2:4 Concrete Reinforcing Steel	Dr. Area 35 A C = 0.5 11.11 C Y @ \$14.50 per C Y 977 Lbs. @ \$.038 Per Lb.	\$ 161.10 37.13 Total 198.23
-----	--	--	---------------------------------------

(4)	Bet. Secs. 17-18, T 20 N., R 14 E; Double 10' x 4' x 26' BC 5A Box Culvert 1:2:4 Concrete Reinforcing Steel	Dr. Area 700 A C = 0.5 66.52 C Y @ \$14.50 Per C Y 6018 Lbs. @ \$.038 Per Lb.	\$ 964.54 228.68 TOTAL 1,193.22
-----	--	--	--

(5)	Bet. Secs. 11-12, T 20 N., R 13 E. Double 4' x 2' -6" x 30' BC 5A Box Culvert 1:2:4 Concrete Reinforcing Steel	Dr. Area - Mohawk Park. 25.69 C Y @ \$14.50 Per C Y 2166 Lbs. @ \$.038 Per Lb.	\$ 372.51 82.31 Total 454.82
-----	---	--	---------------------------------------

(6)	Bet. Secs. 12-13 T 20 N., R 12 E. 3' x 2' -6" x 26' BC 5 Box Culvert. 1:2:4 Concrete Reinforcing Steel	Dr. Area 20 A C = 0.6 10.06 C Y @ \$14.50 per C Y 807 Lbs @ \$.038 Per Lb.	145.87 30.67 Total 176.54
-----	---	---	------------------------------------

(7)	Bet. Secs. 12-13, T 20 N., R 12 E. 3' x 2' -6" x 26' BC 5 Box Culvert 1:2:4 Concrete Reinforcing Steel	Dr. Area 20 A C = 0.6 10.06 C Y @ \$14.50 Per C Y 807 Lbs. @ \$.038 per Lb.	145.87 30.67 Total 176.54
-----	---	--	------------------------------------

(8)	Bet. Secs. 12-13, T 20 N., R 12 E. 2' x 2' x 34' BC 5 Box Culvert 1:2:4 Concrete Reinforcing Steel	Dr. Area 10 A C = 0.6 9.04 C Y @ \$14.50 C Y 804 Lbs. @ \$.038 Per Lb.	131.08 30.55 Total 161.63
-----	---	---	------------------------------------

(9)	Bet. Secs. 12-13, T 20 N., R 12 E. Double 10' x 8' x 26' BC 5A Box Culvert 1:2:4 Concrete Reinforcing Steel	Dr. Area 1700 A C = 0.6 97.53 C Y @ \$14.50 Per C Y 7676 Lbs. @ \$.038 per Lb.	1,414.19 291.69 Total 1,705.88
-----	--	---	---

(10)	Bet. Secs. 13-14, T 20 N., R 12 E. 2' x 2' x 106' BC 6 Box Culvert County will excavate ditch roughly - Contractor to shape up ditch for colvert. 1:2:4 Concrete Reinforcing Steel	Dr. Area 40 A C = 1.0 Sta 53 1/2 35 22.36 C Y @ \$14.50 per C Y 2196 Lbs @ \$.038 Per Lb.	324.22 83.45 Total 407.67
------	--	---	------------------------------------