

10" -7" -10" thick, 1:2:3½ Mixture,
Tulsa County Portland Cement Reinforced
Concrete Paving, including all Reinforcing
shown on Standard Plan and on Special Plan.
Metal Center Strips and Pins, Asphalt Joints,
etc. Complete as per attached plans and
Sections. Coarse Aggregate for Concrete to
be Crushed Limestone.

Approx. 666.7 Sq.Yds. @ \$1.73 Per Sq.Yd. \$ 1,153.39

EXTRA REINFORCING OVER DEEP FILL:
Sta. 174 + 50 to 175 + 50

Approx. 2,780 Lbs. @ .04 Per Lb. 111.20

LIP CURB:

Approx. 500 Lin.Ft. @ 15¢ per L.F. 75.00

FINE GRADING:

Grading to subgrade, shaping and rolling
the same and constnction of shoulders after
completion of Paving; Cleaning out side
ditches, etc. To be paid for according
to the number of square yards of Paving
laid. All payment for Grading to be
covered by the price for Fine Grading.

Approx. 666.7 Sq.Yds. @ \$.10 Per Sq.Yd. 66.67

TOTAL JOB NO. 2. \$ 1,406.26

JOB NO. 3.

PROPOSAL FOR PAVING AND OTHERWISE
IMPROVING 341.5 LIN FEET and CON-
NECTING CURVES ON NORTH CINCINNATI
STREET, FROM APACHE STREET TO MOHAWK
BOULEVARD, BETWEEN SECTIONS 24, T 20 N.,
R 12 E., AND SECTION 19, T 20 N., R 13 E.

IN DAWSON TOWNSHIP.

APPROXIMATE QUANTITIES.

PAVING:

341.5 Lin.Feet of 20 Feet Wide,
9" -6" -9" thick, 1:2:3½ Mixture,
Tulsa County Portland Cement Reinforced
Concrete Paving with Curves, including
all reinforcing, Metal Center Strips and
Pins, Asphalt Joints, etc. Complete as
per attached Plan and Section. Coarse
Aggregate for Concrete to be Crushed
Limestone.

Approx. 1,275. Sq.Yds. @ \$1.73 Per Sq.Yd. \$ 2,205.75

FINE GRADING:

Grading to subgrade, shaping and Rolling the same
and construction of shoulders after completion of
Paving; Cleaning out side ditches, etc. To be
paid for according to the number of sqyare yards of
Paving laid. All payment for Grading to be covered
by the price of Fine Grading.

Approx. 1,275 Sq.Yds @ \$.10 Per Sq.Yd. 127.50

TOTAL JOB. NO. 3. \$ 2,333.25

JOB NO. 4.

PROPOSAL FOR PAVING AND OTHERWISE
IMPROVING 2,600 LIN FEET BETWEEN
SECTIONS 5-6, T 19 N., R 12 E, NORTH
OF BRUNER STATION. Sta. 290. + 50
to Sta. 226 + 50

IN WEKIWA TOWNSHIP.

APPROXIMATE QUANTITIES.

PAVING:

2,600 Lin.Feet of 20 Feet Wide.
9" -6" -9" thick, 1:2:3½ Mixture
Tulsa County Portland Cement Reinforced
Concrete Paving including all Reinforcing,
Metal Center Strips and Pins, Asphalt Joints
etc. Complete as per attached Plan and Section.
Coarse Aggregate for Concrete to be Crushed
Limestone.

Approx. 5,778 Sq.Yds. @ \$1.57 Per Sq.Yd. 9,071.46