

LIP CURB:

Approx. 5,200 Lin.Ft. @ \$00.15 Per Lin.Ft. \$ 780.00

GRADING AND FINE GRADING:

Grading to subgrade, shaping and rolling the same and construction of shoulders after completion of Paving, construction of side ditches, etc. All Payment for Grading and Fine Grading to be covered by the price for Grading.

Approx.

Earth Excavation 1,036 C Y @ \$ .50 per C Y 518.00  
Earth Borrow 166 C Y @ \$ .50 Per C Y 83.00

TOTAL JOB NO. 4. \$ 10,452.46

JOB NO. 5.  
PROPOSAL FOR PAVING AND OTHERWISE IMPROVING 1,200 LIN FEET on NORTH AND SOUTH CENTER LINE OF SECTION 27, T 19 N., R 12 E., ON SOUTH 25TH.WEST AVENUE Sta. 13 + 50 to Sta 25 + 50

IN RED FORK TOWNSHIP.

APPROXIMATE QUANTITIES.

PAVING:

1,200 Lin.Feet of 20 feet wide, 9" -6" -9" thick, 1:2:3½ Mixture Tulsa County Portland Cement Reinforced Concrete Paving including all Reinforcing Metal Center Strips and Pins. Asphalt Joints, etc. Complete as per attached Plan and Section. Coarse Aggregate for Concrete to be cruched Limestone.

Approx. 2,667 Sq.Yds. @ \$1.59 Per Sq.Yd. \$ 4,240.53

LIP CURB:

Approx. 2,400 Lin.Ft. @ \$00.15¢ per Lin.Ft. 360.00

FINE GRADING:

Grading to subgrade, shaping and rolling the same and construction of shoulders after completion of Paving; cleaning out side ditches, etc. To be paid for according to the number of square yards of Paving laid. All Payment for Grading to be covered by the price for Fine Grading.

Approx. 2,667 Sq.Yds. @\$00.08 Per Sq.Yd. 213.36

TOTAL JOB NO. 5. \$ 4,813.89

JOB NO. 6.

PROPOSAL FOR PAVING AND OTHERWISE IMPROVING 4,800 LIN FEET SOUTH FROM THE SOUTH END OFMPAVEMENT IN PLACE IN MILE 4, SECTION "Z-1" ON TURKEY MOUNTAIN ROAD, BETWEEN SECS. 2 and 3, T 18 N., R 12 EAST.

IN JENKS TOWNSHIP.  
APPROXIMATE QUANTITIES.

PAVING:

4,800 Lin.Feet of 20 Feet Wide, 9" -6" -9" thick, 1:2:3½ Mixture Tulsa County Portland Cement Reinforced Concrete Paving including all Reinforcing Metal Center Strips and Pins, Asphalt Joints, etc. Complete as per attached Plan and Section. Coarse Aggregate for Concrete to be Crushed Lime-stone.

Approx. 10,667 Sq.Yds. @ \$1.58 Per S q.Yd. \$ 16,853.86

LIP CURB:

Approx. 7,600 Lin.Ft. @ \$00.15¢ Per Lin.Ft. 1,140.00

FINE GRADING:

Grading to subgrade, shaping and rolling the same and construction of shoulders