

General Grading
(Including Rolling)

Earth Excavation	3,600.0 Cu Yds @	.36¢ per Cu Yd	\$ 1,296.00
Earth Borrow	750.0 Cu Yds @	.36¢ per Cu Yd	270.00
Overhaul	500.0 Cu Yds	.05 Per cu Yd	<u>25.00</u>
Total for general grading			\$ 1,591.00

PAVING

Note:- "Paving is to include the necessary fine grading, and no allowance will be made therefor. Included in the general grading, is the reconstruction of shoulders proper shaping of ditches and slopes to the typical plan and cross section".

We propose to pave with concrete according to Tulsa County Standard Plan, 1:2:3 Mixture Concrete (Crushed Stone Coarse Aggregate), Modified Bates Type, 10"-7"-10" Thickness, expansion joints Fifty (50') feet apart, complete and in place.

Est.	10,800 Sq.Yds @	\$2.26 Per Sq.Yd	\$24,408.00
Total including grading			25,999.00

We propose to pave with concrete Oklahoma Standard Plan, Bates Type 1:2:3½ Mixture (Crushed Stone Coarse Aggregate) 9"-6"-9" Thickness Expansion Joints Fifty (50') feet apart, Complete and in place

Est	10,800 Sq.Yds @	\$2.06 per Sq.Yd	\$22,248.00
Total including grading			23,839.00

Note:- Gravel as Coarse aggregate may be used only when meeting the approval of the County Engineer.

If awarded the contract, we agree to begin the said work within five (5) days from this date and to complete all the said work within fifty (50) working days from date of beginning, or pay to Tulsa County as acknowledged liquidated damages the sum of \$25.00 per day for each day thereafter that the work remains uncompleted.

Certified Check amounting to \$2,000.00 being approximately 5% of the sum bid is hereto attached, conforming to the requirements of the specifications.

Submitted this first day of March, 1926.

SAM WARD PAVING CO, Contractor.
By: Sam Ward.

PROPOSAL NO.4.

PROPOSAL FOR GRADING MILE 8, of SECTION "B", Tulsa County Highway.

Hon. County Commissioners,
Tulsa County, Oklahoma.

Gentlemen:

The undersigned, being familiar with the work proposed to be done in connection with the grading to profile grade the revised alignment of Mile 8, Section "B" Tulsa County Highway, which includes the excavating of material, both from the right of way and from borrow pits to be furnished by Tulsa County, for the making of fills, approaches to bridges, curbing of drainage ditches if ordered, and the general grading of the roadbed, proposes to furnish all labor and equipment and to perform the said work according to the stakes and under the direction of the County Engineer, at the following unit item prices, including clearing and grubbing:

Earth Excavation	2,511.0 Cu Yds. @	\$.24¢ per Cu Yd	\$ 602.64
Earth Borrow	9,476.9 Cu Yds @	.25¢ per Cu Yd	2,369.22
Overhaul	3,500.0 Cu Yds	.06¢ per Cu Yd	<u>210.00</u>
Total			\$3,181.86

Force account, or extra work as may be ordered to be paid for at actual cost plus fifteen (15) per cent.

If awarded the contract, we agree to begin the said work within ten (10) days and to complete all the said work within forty five (45) working days. (Oklahoma Standard Specifications govern)

Certified check amounting to \$160.00 being approximately 5% of the sum bid is hereto attached, conforming to instructions and the specifications.

Submitted this 1st. day of March, 1926.

John Cronin, Contractor.