

(8)	Bet. Secs. 1-12, T 20 N., R 12 E. 3' x 38' x 26' BC 5 R C Box Culvert 1:2:4 Concrete Reinforcing Steel	Dr. Area 40 A. A C = 0.5 11.29 C Y @ \$15.50 per C Y 914 Lbs. @ .04½ Per Lb.	\$ 174.99 38.84 \$ 213.83
(9)	Bet. Secs. 6-7, T 20 N., R 13 E. #3' x 2' x 30' BC 5 R C Box Culvert 1:2:4 Concrete Reinforcing Steel	Dr. Area 25 A. A C = 0.5 9.78 C Y @ \$16.00 per C Y 851 Lbs. @ .04½ per Lb.	\$ 156.48 36.17 \$ 192.65
(10)	Bet. Secs. 6-7, T 20 N., R 13 E. 5' x 2'-6" x 26' BC 5 R C Box Culvert 1:2:4 Concrete Reinforcing Steel	Dr. Area 75 A. C = 0.5 14.42 C Y @ \$16.00 per C Y 1257 Lbs. @ .04½ per Lb.	\$ 230.00 53.42 \$ 284.14
(11)	Bet. Secs. 5-8, T 20 N., R 13 E. 4' x 2'-8" x 26' BC 5 R C Box Culvert 1:2:4 Concrete Reinforcing Steel	Dr. Area 50 A. C = 0.5 12.30 C Y @ \$16.00 per C Y 1025 Lbs. @ .04½ Per Lb.	\$ 196.80 43.56 \$ 240.36
(12)	Bet. Secs. 5-8, T 20 N., R 13 E. 28' -30" R C Pipe Culvert County to furnish pipe at site of work. Installing 30" R C Pipe 28 L F @ \$1.30 Per L F 1:2:4 Concrete Reinforcing Steel	Dr. Area 20 A. C = 0.5 2.77 C Y @ \$17.00 per C Y 62 Lbs. @ .04½ per Lb.	\$ 36.40 47.09 2.63 \$ 86.12
(13)	Bet. Secs. 18-19, T 20 N., R 13 E. 4' x 4' x 32' BC 5 R C Box Culvert 1:2:4 Concrete Reinforcing Steel	Dr. Area 75 A. C = 0.6 20.63 C Y @ \$16.50 per C Y 1527 Lbs. @ .04½ Per Lb.	\$ 340.39 64.90 \$ 405.29
(14)	Bet. Secs. 18-19, T 20 N., R 13 E. 3' x 3' x 26' BC 5 R C Box Culvert 1:2:4 Concrete Reinforcing Steel	Dr. Area 30 A. C = 0.6 11.29 C Y @ \$16.50 per C Y .04½ Per Lb.	\$ 186.28 38.84 \$ 225.12
(15)	Bet. Secs. 18-19, T 20 N., R 13 E. 3' x 2'-6" x 32' BC 5 R C Box Culvert 1:2:4 Concrete Reinforcing Steel	Dr. Area 25 A. C = 0.6 11.50 C Y @ \$16.50 per C Y 950 Lbs. @ .04½ Per Lb.	\$ 189.75 40.38 \$ 230.13
HARVARD AVENUE			
(16)	Bet. Secs. 20-21, T 20 N., R 13 E. 56' -24" R C Pipe Culvert County to furnish pipe at site of work Installing 24" R C Pipe 56 L F @ 1:2:4 Concrete Reinforcing Steel	Dr. Area 10 A C = 0.5 \$ 0.95 per L F \$17.50 per C Y @ .04½ per L B	\$ 53.20 36.40 2.38 \$ 91.98
(17)	Bet. Secs. 20-21, T 20 N., R 13 E. 56' -18" R C Pipe Culvert County to furnish pipe at site of work. Installing 18" R C Pipe 56 L F @ \$.80 per L F 1:2:4 Concrete Reinforcing Steel	\$ 44.80 25.73 1.19 Total	\$ 71.72
(18)	Bet. Secs. 20-21, T 20 N., R 13 E. 6' x 2' x 56' BC 5 R C Box Culvert 1:2:4 Concrete Reinforcing Steel	Dr. Area 25 A. C = 0.5 29.19 C Y @ \$ 16.00 per C Y 2770. Lbs. @ .04½ Per Lb.	\$ 467.04 117.72 \$ 584.76
(19)	Bet. Secs. 28-29, T 20 N., R 13 E. 6' x 3' x 20' Slap Top Culvert Extend to 6' x 3' x 56' - Extension to be BC 5 R C Box 1:2:4 Concrete Reinforcing Steel	Dr. Area A. C = 0.5 24.33 C Y @ \$16.00 per C Y 2009 Lbs. @ .04½ Per Lb.	\$ 389.28 85.38 \$ 474.66
(20)	Bet. Secs. 28-29, T 20 N., R 13 E. 56' -24" R C Pipe Culvert County to furnish pipe at site of work. Installing 24" R C Pipe 1:2:4 Concrete Reinforcing Steel	Dr. Area 12 A. C = 0.5 56 L F @ \$ 0.95 per L F 2.08 C Y @ \$17.50 per CY 56 Lbs. @ .04½ Per Lb.	\$ 53.20 36.40 2.38 \$ 91.98
(21)	Bet. Secs. 28-29, T 20 N., R 13 E. 4' x 3' x 56' BC 5 R C Box Culvert 1:2:4 Concrete Reinforcing Steel	Dr. Area 60 A. C = 0.5 23.40 C Y @ \$15.50 per C Y 2142 Lbs. @ .04½ Per Lb.	\$ 362.70 91.03 \$ 453.73
(22)	Bet. Secs. 32-33, T 20 N., R 13 E. 8' x 3' x 26' BC 5 Extend to 8' x 3' x 44' BC 5 R C Box Culv. U Type ends. 1:2:4 Concrete Reinforcing Steel	Dr. Area 175 A. C = 0.5 17.61 per C Y @ \$15.50 per C Y 1528 Lbs. @ .04½ per Lb.	272.95 64.94 \$ 337.89