

(36)	Bet. Secs. 26-35, T 20 N., R 13 E. 4' x 2' x 30' BC 5 R C Box Culvert 1:2:4 Concrete Reinforcing Steel	Dr. Area 40 A. C = 0.5 12.27 C Y @ \$15.50 per C Y 1099 Lbs. @ .04½ Per Lb.	\$ 190.18 46.71 \$ 236.89
(37)	Bet. Secs. 26-35, T 20 N., R 13 E. 5' x 2' x 30' BC 5 R C Box Culvert 1:2:4 Concrete Reinforcing Steel	Dr. Area 60 A. C = 0.5 15.91 C Y @ \$15.50 per C Y 1411 Lbs. @ .04½ Per Lb.	\$246.60 59.97 \$306.57
(38)	Bet. Secs. 26-35, T 20 N., R 13 E. 3' x 2' x 30' BC 5 R C Box Culvert. 1:2:4 Concrete Reinforcing Steel	Dr. Area 25 A. C = 0.5 9.78 C Y @ \$15.50 per C Y 851. Lbs. @ .04½ per Lb.	\$ 151.59 361.17 187.76
(39)	Bet. Secs. 26-35, T 20 N., R 13 E. Double 10' x 4' x 30' BC 5A R C Box Culvert 1:2:4 Concrete Reinforcing Steel	Dr. Area 850 A. C = 0.5 74.12 C Y @ \$15.50 per C Y 6801 Lbs. @ .04½ Per Lb.	\$1148.86 289.04 \$1437.90
(40)	Bet. Secs. 25-36, T 20 N., R 13 E. 32" 18" R C Pipe Culvert County to furnish pipe at site of work. Installing 18" R C Pipe 1:2:4 Concrete Reinforcing Steel	32 L F @ \$.80 per L F 1.47 C Y @ \$17.00 per C Y .28 Lbs. @ .04½ per Lb.	\$ 25.60 24.99 1.19 \$ 51.78
(41)	Bet. Secs. 25-36, T 20 N., R 13 E. 8' x 3' x 30' BC 5 R C Box Culvert 1:2:4 Concrete Reinforcing Steel	Dr. Area 175 A. C = 0.5 29.09 C Y @ \$16.00 per C Y 2620 Lbs. @ .04½ per Lb.	\$ 465.44 111.35 \$ 576.79
(42)	Bet. Secs. 25-36, T 20 N., R 13 E. 3' x 2' x 30' BC 5 R C Box Culvert 1:2:4 Concrete Reinforcing Steel	Dr. Area 35 A. C = 0.5 11.02 C Y @ \$16.00 per C Y 902 Lbs. @ .04½ Per Lb.	\$ 176.32 38.33 \$ 214.65
(43)	Bet. Sec. 25-36, T 20 N., R 13 E. 8' x 2' x 30' BC 5 R C Box Culvert 1:2:4 Concrete Reinforcing Steel	Dr. Area 100 A. C = 0.6 27.40 C Y @ \$16.00 per C Y 2540 Lbs. @ .04½ Per Lb.	\$ 438.40 107.95 \$ 546.35

(44)	Bet. Secs. 7-18, T 20 N., R 14 E. 6' x 2' x 26' BC 5 R C Box Culvert 1:2:4 Concrete Reinforcing Steel	Dr. Area 100 A C = 0.5 18.00 C Y @ \$17.00 per C Y 1512 Lbs. @ .04½ per Lb.	\$ 306.00 64.26 \$ 370.26
(45)	Bet. Secs. 19-30, T 20 N., R 14 E. 5' x 2' x 26' BC 5 R C Box Culvert 1:2:4 Concrete Reinforcing Steel	Dr. Area 50 A. C = 0.5 13.15 C Y @ \$15.00 per C Y 1176 Lbs. @ .04½ per Lb.	\$ 197.25 49.98 \$ 247.23
(46)	Bet. Secs. 19-30, T 20 N., R 14 E. 1:2:4 Conc. 6' x 2' x 26' BC 5 R C Box Culvert. 1:2:4 Concrete Reinforcing Steel	Dr. Area 62 A C = 0.5 15.95 C Y @ \$15.00 Per C Y 1412 Lbs. @ .04½ Per Lb.	\$ 239.25 60.01 \$ 299.26
(47)	Bet. Secs. 20-29, T 20 N., R 14 E. 2' x 2' x 26' BC 5 R C Box Culvert. 1:2:4 Concrete Reinforcing Steel	Dr. Area 12 A. C = 0.6 7.56 C Y @ \$ 16.00, per C Y 650 Lbs. @ .04½ per Lb.	\$ 120.96 27.62 \$ 148.58
(48)	Bet. Secs. 20-29, T 20 N., R 14 E. Triple 16' x 4' x 24' Slab Top R C Bridge. Two (2) Abutments. 1:2:4 Concrete Reinforcing Steel	Dr. Area 3000 A C = 0.5 41.7 C Y @ \$16.00 per C Y 2284 Lbs. @ .04½ Per Lb.	 \$ 667.20 97.07
	Two (2) Piers 1:2:4 Concrete Reinforcing Steel	19.24 C Y @ \$17.00 per C Y 1428 Lbs. @ .04½ per Bb.	\$ 327.08 60.69
	Floor System 1:2:4 Concrete Reinforcing Steel	72.90 C Y @ \$17.00 per C Y 8062 Lbs. @ .4½ per Lb.	1,239.30 342.63
	Handrail Complete, including Posts, Reinforcing and Double Precast Rails 2½" Drain Pipe Two 1" Asphalt Joints, Lump Sum	110.7 L F @ \$ 2.50 per L F 7. L F .50 Per L F	\$ 276.75 3.50 5.00
	Total		\$ 3,019.22