

Installing 18" R C Pipe		28 L F @ \$.80 per L F	\$ 22.40
1:2:4 Concrete		1.47 C Y @ \$18.50 per C Y	27.19
Reinforcing Steel		28 Lbs. @ .04 $\frac{1}{4}$ Per Lb.	1.19
		Total	50.78
(20)	Bet. Secs. 25-36, T 21, R 13.	Dr. Area 500 A. C = 0.6	
Double 8' x 4' x 26' BC 5 A R C Box Culvert with Special Wing.			
1:2:4 Concrete		54.00 C Y @ \$15.75 per C Y	\$ 850.50
Reinforcing Steel		4629 Bbs. @ .04 $\frac{1}{4}$ per Lb.	196.73
		Total	1,047.23
(21)	Bet. Secs. 25-36, T 21, R 13.	Dr. Area 75 A. C = 0.7	
6' x 3' x 26' BC 5 R C Box Culvert with Special Wing.			
1:2:4 Concrete		20.06 C Y @ \$15.75 Per C Y	\$ 315.95
Reinforcing Steel		1611 Lbs. @ .04 $\frac{1}{4}$ Per Lb.	68.47
		Total	\$ 384.42
(22)	Bet. Secs. 10-15, T 21, R 13.		
2' x 2' x 26' BC 5 R C Box Culvert			
1:2:4 Concrete		7.56 C Y @ \$18.50 per C Y	\$ 139.86
Reinforcing Steel		650 Lbs. @ .04 $\frac{1}{4}$ per Lb.	27.62
		Total	\$ 167.48
(23)	Bet. Secs. 10-15, T 21, R 13		
2' x 2' x 26' BC 5 R C Box Culvert			
1:2:4 Concrete		7.56 C Y @ \$18.50 Per C Y	\$ 139.86
Reinforcing Steel		650 Lbs. @ .04 $\frac{1}{4}$ per Lb.	27.62
		Total	\$ 167.48
(24)	Bet. Secs. 11-14, T 21, R 13.		
28'-18" R C Pipe Culvert.			
County to furnish pipe at site of work.			
Installing 18" R C Pipe		28 L F @ \$.80 Per L F	\$ 22.40
1:2:4 Concrete		1.47 C Y @ \$20.00 per C Y	29.40
Reinforcing Steel		28 Lbs. @ .04 $\frac{1}{4}$ per Lb.	1.19
		Total	52.99
(25)	Bet. Secs. 11-14, T 21, R 13.	Dr. Area 120 A. C = 0.5	
5' x 4' x 26' BC 5 R C Box Culvert.			
1:2:4 Concrete		20.25 C Y @ \$18.50 per C Y	\$ 374.62
Reinforcing Steel		1515 Lbs. @ .04 $\frac{1}{4}$ Per Lb.	64.39
		Total	\$ 439.01
(26)	Bet. Secs. 11-14, T 21, R 13.	Dr. Area 30 A. C = 0.6	
4' x 2' x 27' BC 5 R C Box Culvert			
1:2:4 Concrete		11.11 C Y @ \$18.50 per C Y	\$ 205.53
Reinforcing Steel		977 Lbs. @ .04 $\frac{1}{4}$ Per Lb.	41.52
		Total	247.05
(27)	Bet. Secs. 11-14, T 21, R 13.	Dr. Area 50 A. C = 0.6	
4' x 3' x 26' BC 5 R C Box Culvert			
1:2:4 Concrete		13.59 C Y @ \$18.50 per C Y	\$ 251.41
Reinforcing Steel		1134 Lbs. @ .04 $\frac{1}{4}$ per Lb.	48.20
		Total	\$ 299.61
(28)	Bet. Secs. 11-12, T 21, R 13.	Dr. Area 20 A. C = 0.5	
3' x 2' x 30' BC 5 R C Box Culvert			
1:2:4 Concrete		9.78 C Y @ \$18.50 per C Y	\$ 180.93
Reinforcing Steel		851 Lbs. @ .04 $\frac{1}{4}$ per Lb.	36.19
		Total	217.12
(29)	Bet. Secs. 13-14, T 21, R 13.	Dr. Area 25 A.	
4' x 2' x 30' BC 5 R C Box Culvert			
1:2:4 Concrete		12.27 C Y @ \$18.50 per C Y	\$ 226.99
Reinforcing Steel		1099 Lbs. @ .05 Per Lb.	54.95
		Total	\$ 281.94
(30)	Bet. Secs. 22-23, T 21, R 13.	Dr. Area 380 A. C = 0.5	
Double 8' x 3' x 20' BC 5A R C Box Culvert. - U Type Ends.			
1:2:4 Concrete		38.79 C Y @ \$17.25 Per C Y	\$ 669.13
Reinforcing Steel		3417 Lbs. @ .04 $\frac{1}{4}$ Per Lb.	145.22
		Total	\$ 814.35
(31)	Bet. Secs. 22-23, T 21, R 13.	Dr. Area. 110 A. C = 0.5	
5' x 3'-6" x 20" BC 5 R C Box Culvert U Type Ends.			
1:2:4 Concrete		13.35 C Y @ \$17.25 per C Y	\$ 230.29
Reinforcing Steel		1137 Lbs. @ .04 $\frac{1}{4}$ Per Lb.	48.32
		Total	278.61
(32)	Bet. Secs. 8-9 T 21, R 14.	Dr. Area 40 A. C = 0.5	
4' x 2' x 20' BC 5 R C Box Culvert		U Type Ends.	
1:2:4 Concrete		8.16 C Y @ \$17.75 per C Y	\$ 144.84
Reinforcing Steel		759 Lbs. @ .04 $\frac{1}{4}$ per Lb.	32.26
		Total	177.10
(33)	Bet. Secs. 8-9 T 21, R 14.	Dr. Area 10 A C = 0.5	
24'-24" R C Pipe Culvert.			
County to furnish pipe at site of work.			
Installing 24" R C Pipe 24 L F @ \$ 0.95 Per L F			\$ 22.80
1:2:4 Concrete		2.08 C Y @ \$19.00 per C Y	39.52
Reinforcing Steel		56 Lbs. @ 0.04 $\frac{1}{4}$ Per Lb.	2.39
		Total	64.71