PROPOSAL FOR CONSTRUCTION OF 362 Ft. Treated Timber Pile Trestle 19 Spans 19'-0" with 18' Roadway, as per plans and Specifications.

Honorable Board of County Commissioners, Tulsa County, Oklahoma.

Gentlemen:

The undersigned having examined the plans and specifications, the location and character of the work proposed to be done and per ormed in the construction of the herein described Drainage Structure, hereby proposes to furnish PLANT, TOOLS AND LABOR for the complete exection as per plan and specifications of a Treated Timber Pile Trestle Three Hundred Sixty Two (362') Feet long (19 -19 Ft.Spans with 18 Ft.Roadway) between Sections Five (5) and Eight (8), Township Twenty (20) North, Range Fourteen (14) East, Tulsa County, Oklahdma.

Tulsa County will furnish all Lumber and Piles F O B Cars at Owasso, Oklahoma, and all Hardware, Paint and other materials that may be needed at the site of the work. Tulsa County will also place the Asphalt covering on the wooden floor of the bridge. The Lumber and Piling will be unloaded from the cars and hauled to the site of the work by the Contractor; the cost of this work being included in the bid prices.

If the quantity of the work is increased or diminished, it is understood that the same unit prices will prevail.

Especial care must be taken in driving Piles that the Piles are not damaged in any way, that none of them are driven below grade and that they are in true position as nearly as possible. Payment on handling and driving Piles will be made on the basis of the length of the Pile after being sawed off. The Piles as ordered are thirty four (34) feet long.

The Contractor hereby agrees to assume all responsibility for the Lumber and Piles from the time they reach Owasso until the trestle is completed, and all other materials from the time they are delivered on the work until completion of the trestle.

All work to be done according to the plans and specifications and to the stakes and under the direction of the County Engineer or his authorized representatives (Oklahoma State Standard Specifications to govern) which price as bid includes the structure complete and in place, at the unit item prices set opposite, viz, to-wit:

WORK TO BE DONE

Item #1. Furnishing Plant, tools and Labor, handling, Driving and Sawing off Piles. 100 Piles 34 Ft.Long.

3200 L F @ \$.45 per L F

\$ 1,440.00

ITEM # 2 Furnishing Plant, tools and Labor for handling Lumber and other materials for the complete erection of the Pile Trestle (except Item #1), including Boring and Treating all bolt holes in the Piles and connecting timbers and in the floor, and all fastening together of timbers and sawing bridging pirces to length.

77,860 Ft.BM Lumber in place in Structure \$ \$15.00 per M Ft.BM

1,167.90

Item #3. Furnishing Tools and Labor for painting handrail and posts three (3) coats of White Paint LUMP SUM

181,00

GRAND TOTAL FOR COMPLETED STRUCTURE IN PLACE.

\$ 2,788.90

Force Account, or Extra Work, only when ordered in writing by the County Engineer. at ACTUAL COST, Plus Ten (10%) Per Cent.

If awarded the said work, we propose to immediately enter into contract, furnishing acceptable Surety Company Bonds, both Contracttand Statutory, in the full amount of the Contract prices, agreeing to beginthe said work wirhin Five (5) days after work order is issued by the County Engineer, and to complete the same to your acceptance within Thirty (30) working days after said work order is issued by the County Engineer.

Upon failure to complete within the time limit as proposed, we agree to all the provisions embodied in the Oklahoma State Standard Specifications respecting failure to complete within the specified time as bid.

Certified Check or Bidder's Bond amounting to \$250.00 being approximately 10% of the sum bid and conforming to the "Notice to Contractors" and specification provisions, is hereto attached.

NOTE: Attention is called to the provision embodied in the published "Notice to Contractors" that proposal must be on forms prepared by the County Engineer.

Respectfully submitted this 24th. day of February, 1931.
218 North Boulder.
Tulsa, Okla.

Respectfully submitted this 24th. day of February, 1931.

McCONNELL AND ROOP, Contractor
By: M A Roop, Supt.