

526	Lin.Ft. 60" Monolithic Reinf. Concrete Sewer, complete, in place Types "M" and "N" exclusive of Reinforcing Steel	@\$5.00 per Lin Ft.	\$ 2,630.00
308	Lin Ft. 60" Monolithic Reinf. Concrete Sewer, complete in place Type "O", exclusive of Reinforcing Steel	@\$7.00 prt Lin Ft.	2,156.00
47,700	Lbs. Reinforcing Steel for Sewers, in place	@\$0.03 per Lb.	1,431.00
72	Cu.Yds. 1:2:3 Concrete in Junction Chambers, Inlets and Endwall	@\$12.00 per C Y	864.00
7,940	Lbs. Reinforcing Steel, in place in Junction Chambers, Inlets and Endwall	@\$0.03 per Lb.	238.20
900	Cu.Yds. Earth Excavation	@\$0.50 Per Cu Yd.	450.00
900	Cu.Yds Loose Rock Excavation	@\$0.50 per C Y	450.00
1,560.	Cu.Yds Solid Rock Excavation	@\$0.50 per C Y	780.00
TOTAL			\$ 11,184.60

ALTERNATE BID

672	Lin Ft. 48" Precast R C Pipe laying, complete, in place	@\$0.65 per Lin Ft.	\$ 436.80
-----	--	---------------------	-----------

FORCE ACCOUNT, or Extra Work, only
when ordered in writing by the
Engineer at ACTUAL COST, Plus Fifteen
(15%) Per Cent.

SPECIAL PROVISIONS

Excavation will be computed and paid for as outlined in Section 59, Tulsa City Specifications for Storm Sewers, February, 1928.

Classification for excavation will be as defined in Section 77, Tulsa City Specifications for Storm Sewers, February, 1928.

A certain portion of the Excavation for this work will be done by Tulsa County.

Tulsa County will furnish at the site of the work all the Precast Reinforced Concrete Pipe used in the work.

The materials in the Concrete used in the construction of Monolithic Reinforced Concrete Sewers and of the auxiliary structures shall be mixed in the following proportions, by volume: One (1) Part Portland Cement, Two (2) Parts Sand, Three (3) parts Crushed Stone.

Concrete mixed in transit will be permitted, provided the method of proportioning and mixing meets the approval of the County Engineer.

In excavating trench for Precast Pipe in rock, the rock shall be excavated about three (3") inches below grade and the trench re-filled with earth a sufficient depth so that when tamped the earth affords an even surface for the pipe to rest upon throughout its length.

After the precast reinforced concrete pipe is laid and the joints are filled as prescribed in the Tulsa City Specifications, the Contractor shall backfill the trench with earth to the horizontal line through the center of the pipe, and thoroughly flush the earth fill to insure that all voids are filled and that the pipe is properly supported. Water for flushing will be furnished by the Fair Board.

The material excavated from the trench shall be dumped on the side of the trench as directed by the County Engineer.

After the sewer is laid, the trench shall be back-filled by the Contractor, as directed in Tulsa City Specifications, to the level of the original ground.

Any excess material will be left on the ground and will be handled by Tulsa County.

If awarded the said work, we propose to immediately enter into Contract, furnishing acceptable Surety Company Bonds, both Contract and Statutory, in the full amount of the Contract Price, agreeing to begin the said work within Five (5) days after WORK ORDER is issued by the County Engineer, and to complete the same to your acceptance within Forty (40) Working days after said Work Order is issued by the County Engineer.

Upon failure to begin, or complete, the said work within the time limit as proposed we agree to all the provisions embodied in the "City of Tulsa Specifications for Storm Sewers, revised February 1928", respecting failure to begin or complete within the specified time as bid.

When mutually agreed to by and between your Honorable Board and ourselves, this proposal may be considered for extension to additional work of the same character in the construction of Tulsa State Fair Grounds Drainage System, and as a continuation of the work herein bid upon as though the same were herein originally contained and set out.

Certified Check (or Bidder's Bond) amounting to \$1,119.00 being approximately Ten (10%) Per Cent of the sum bid and conforming to the legal requirements and "Notice to