

<u>North of Oakhurst.</u>		Drainage Area 30 A.	Fast Rolling.
<u>Bet Sec 31-32 Twp.19 N.R 12 E.</u>			
<u>3' x 3' x 26' Con.Box Culvert.</u>			
1:2:4 Concrete	10.1 C Y	@ \$19.00 per C Y	\$ 191.90
Reinforcing Bars	807.0 Lbs	@ .05 per Lb.	40.35
		Total	\$ 232.25

<u>Bet. Sec. 31-32 Twp 19 N.R 12 E.</u>		Drainage Area 300 A	Fast Rolling.
<u>8' x 5' x 26' Conc. Box Culvert.</u>			
1:2:4 Concrete	35.5 C Y	@ \$19.00 per C Y	\$ 674.50
Reinforcing Bars	2740.0 Lbs	@ .05 per Lb.	137.00
		Total	\$ 811.50

<u>Bet. Sec. 28-29 Twp 19 R 12 E.</u>		Drainage Area 60 A.	Mountainous.
<u>1:2:4 Concrete</u>			
	22.0 C Y	@ \$19.00 per C Y	\$ 418.00
Reinforcing Bars	1700.0 Lbs.	@ .05 per Lb.	85.00
		Total	\$ 503.00

<u>Bet. Sec. 28-29- Twp 19 N., R 12 E.</u>		Drainage area 20 A	Hilly.
<u>3' x 2' x 26' Conc.Box Culvert.</u>			
1:2:4 Concrete	8.9 C Y	@ \$ 19.00 per C Y	\$ 169.10
Reinforcing Bars	760.0 Lbs.	@ per Lb	38.00
		Total	207.10

<u>Bet. Sec. 32-33. Twp 19 N., R 12 E.</u>		Drainage Area 150 A.	Hilly.
<u>8' x 3' x 26' Conc.Box Culvert.</u>			
1:2:4 Concrete	26.2 C Y	@ \$19.00 per C Y	\$ 497.80
Reinforcing Bars	2325.0 Lbs.	@ .05 per Lb.	116.25
		Total	\$ 614.05

GRAND TOTAL FOR PROPOSAL \$7,125.64

If awarded the work, we agree to immediately enter into contract, furnishing an acceptable Surety Company Bond, both contract and statutory in the full amount of 100% of the estimated contract price; agreeing to begin the said work within 5 days from this date and to complete the same on or before the 1st. day of December, 1926, and upon failure to do so, agree to the provisions as embodied in the Oklahoma Standard Specifications respecting failure to complete work within the specified time as bid.

Certified Check amounting to \$370.00 being approximately 5% of the sum bid is hereto attached, conforming to "Notice to Contractors and specification provisions.

Respectfully submitted on this 30th. day of August, 1926.

E G Fike and Co. By; E G Fike, Contractor.

PROPOSAL NO.6.

Letting August 30th. 1926.

Honorable County Commissioners,
Tulsa County, Oklahoma.

Gentlemen:

The undersigned, having examined the plans and specifications the location and character of the work proposed to be done and performed in the construction of the hereinafter listed Bridges and Culverts, proposes to furnish all labor and material and equipment and to complete the same according to the plans and specifications and to the stakes and under the direction of the County Engineer or his duly authorized representative which price as bid includes all excavation and the structure complete and in place (Oklahoma Standard Specifications to govern) the following structures at the unit item prices set opposite, viz to-wit:

SKIATOOK TOWNSHIP BRIDGE EAST OF SKIATOOK		
<u>On Road to New Bird Creek Bridge</u>		Drainage Area 2800 A.
<u>40' x 9' x 20' I Beam Bridge</u>		

1:2:3 Concrete	31.0 C Y	@ \$19.80 per C Y	613.00
1:2:4 Concrete	96.0 C Y	@ \$18.80 per C Y	1804.80
Structural Steel	23,744.0 Lbs	@ .06 per Lb	1424.64
Reinforcing Bars	9,000.0 Lbs	@ .055 per Lb.	495.00
3" Black Iron Pipe	164.0 L F	@ .70 per Lb	114.80
2" Black Iron Pipe	28.0 L F	@ .80 per LF	22.40
		Total	\$ 4474.64

DAWSON TOWNSHIP

<u>Bet. Secs. 13-24 Twp. 20 N.R 12 E.</u>		Drainage Area 140 A	Light Hilly.
<u>8' x 3' x 30' Conc.Box Culvert</u>			

1:2:4 Concrete	29.1 C Y	@ \$19.00 per C Y	\$ 552.90
Reinforcing Bars	2620.0 Lbs	@ .05 per Lb	131.00
		Total	\$ 683.90