

## ON ROAD TO MOHAWK RESERVOIR

In Sec. 16, Twp. 20 N., R 13 E. Sta 215 / 85  
5' x 3' -6" x 30' Conc Box Culvert

Drainage Area 90 A. Fast Rolling.

1:2:4 Concrete	20.5 C Y	@ \$ 19.00 per C Y	\$ 389.50
Reinforcing Bars	1600.0 Lbs.	@ .05 per Lb	80.00
		Total	\$ 469.50

In Sec. 16, Twp. 20 N., R 13 E. Sta 220 / 50 Drainage Area 25 A. Fast Rolling.  
3' x 2' x 40' Conc.Box Culvert 4'-6" Fill  
Over Culvert.

1:2:4 Concrete	12.0 C Y	@ \$ 19.00 per C Y	\$ 228.00
Reinforcing Bars	1801.0 Lbs	@ .05 per Lb.	54.05
		Total	282.05

GRAND TOTAL FOR PROPOSAL \$5,910.09

If awarded the work, we agree to immediately enter into contract, furnishing an acceptable Surety Company Bond, both contract and statutory, in the full amount of 100% of the estimated contract price; agreeing to begin the said work within 5 days from this date, and to complete the same on or before the 15th. day of December, 1926 and upon failure to do so agree to the provisions as embodied in the Oklahoma Standard Specifications respecting failure to complete work within the specified time as bid.

Certified Check amounting to \$315.00 being approximately 5% of the sum bid is hereto attached, conforming to "Notice to Contractors" and specification provisions.

Respectfully submitted on this 20th. day of August, 1926.

(Bid based on Grand River Gravel.)

E G FIKE AND CO. Contractor.  
By: E G Fike, Pres.

PROPOSAL NO.7.

Letting August 30th.1926.

Honorable County Commissioners,  
Tulsa County, Oklahoma.

Gentlemen:

The undersigned, having examined the plans and specifications the location and character of the work proposed to be done and performed in the construction of the herein after listed Bridges and Culverts, proposes to furnish all labor, material and equipment and to complete the same according to the plans and specifications and to the stakes and under the direction of the County Engineer or his duly authorized representatives, which price as bid includes all excavation and the structure complete and in place (Oklahoma Standard Specifications to govern) the following structures at the unit item prices set opposite, viz: to-wit:

LYNN LANE TOWNSHIP ON 31ST STREET.

Bet. Sec 18-19, Twp 19 N., R 13 E.  
Double 11' x 10' x 38' Box Culvert-Skewed

1:2:4 Concrete	193.0 C Y	@ \$ 19.00 per C Y	\$ 3667.00
Reinforcing Bars	12,537.0 Lbs.	@ .05 per Lb.	626.85
Earth Excav.	360.0 C Y	@ .85 per C Y	306.00
(To be placed where indicated)			
For removing old superstructure and east abutment		Lump sum	100.00
	(Bid based on crushed stone)	TOTAL	\$ 4699.85

FRYE TOWNSHIP  
WEST OF ARTHUR BYNUM'S CORNER.

Bet Sec.2-11, Twp.18 N., R 13 E.  
8' x 6' x 30' Conc.Box Culvert

Drainage Area 280 A. Fast Rolling.

1:2:4 Concrete	45.0 C Y	@ \$ 19.10 Per C Y	\$ 859.50
Reinforcing Bars	3300.0 Bbs.	@ .05 Per Lb.	ml65.00
		Total	\$1024.50

Bet. Sec. 2-11 Twp. 18 N., R 13 E.  
5' x 4' x 30' Conc.Box Culvert.

Drainage Area 120 A. Fast Rolling.

1:2:4 Concrete	22.2 C Y	@ \$ 19.10 per C Y	\$ 424.02
Reinforcing Bars	1690.0 Lbs.	@ .05 Per Lb.	84.50
	(Bid Based on Gravel)	Total	508.52

Grand total for proposal 6,232.87

If awarded the work, we agree to immediately enter into contract, furnishing an acceptable Surety Company Bond, both contract and statutory, in the full amount of 100% of the estimated contract price; agreeing to begin the said work within 5 days from this date, and to complete the same on or before the 30th day of November 1926, and upon failure to do so, agree to the provisions as embodied in the Oklahoma Standard Specifications respecting failure to complete work within the specified time as bid.

Certified check amounting to \$335.00 being approximately 5% of the sum bid is hereto attached, conforming to "Notice to Contractors" and specification provisions.

Respectfully submitted on thos 30th. day of August, 1926.

E G Fike and Co. Contractor.  
By: E G Fike. President.

PROPOSAL NO.8.

Letting August 30th. 1926.

Honorable County Commissioners, Tulsa County, Oklahoma.