

Bet. Sec's 10-11, T 16 N., R 13 E.		Drainage Area 260 A Rolling.	
6' x 5' -6' x 30' Concrete Box Culvert			
1:2:4 Concrete	34.8 C Y	@ \$ 22.30 Per C Y	\$ 776.04
Reinforcing Steel	2350.0 Lbs	.055¢ Per Lb	129.25
		Total	905.29
Bet. Sec's 10-11, T 16 N., R 13 E.		Drainage Area 170 A Rolling.	
8' x 4' x 30' Concrete Box Culvert			
1:2:4 Concrete	32.6 C Y	@ \$ 22.30 Per C Y	\$ 726.98
Reinforcing Steel	2784.0 Lbs	.055¢ Per Lb.	153.12
		Total	880.10
Bet. Sec's 4-33, T 16-17 N. R 13 E.		Drainage Area 350 A Fast Rolling	
10' x 4' x 30' Concrete Box Culvert		Sta. 308 / 60	
1:2:4 Concrete	39.8 C Y	@ \$ 22.30 Per C Y	\$ 887.54
Reinforcing Bars	3565.0 Lbs	.055 Per Lb.	196.08
		Total	\$ 1083.62
Bet. Sec's 9-16, T 16 N., R 13 E.		Drainage Area 170 A Fast Rolling.	
8' x 3' x 30' Concrete Box Culvert		Sta. 420 / 00	
1:2:4 Concrete	29.1 C Y	@ \$ 23.00 Per C Y	\$ 669.30
Reinforcing Steel	2620.0 Lbs	.055 ¢ Per Lb.	144.10
		Total	\$ 813.40
Bet. Sec's 8-9, T 16 N., R 13 E. About Sta. 432 /		Drainage Area 80 A Rolling.	
5' x 3' x 30' Concrete Box Culvert			
1:2:4 Concrete	17.3 C Y	@ \$ 23.00 Per C Y	\$ 397.90
Reinforcing Steel	1500.0 Lbs.	.055¢ Per Lb.	82.50
		Total	480.40
Bet. Sec's 2-35, T 16-17 N., R 13 E.		Drainage Area 125. A Fast Rolling.	
8' x 2' x 6' x 30' Concrete Box Culvert			
1:2:4 Concrete	27.0 C Y	@ \$ 20.53 Per C Y	\$ 554.31
Reinforcing Bars	2500.0 Lbs	.055¢ Per Lb	137.50
		Total	\$ 691.81
Bet. Sec's 7-12, T 16 N., R 12-13 E.		Drainage Area 60 A Fast Rolling.	
5' x 3' x 36' Concrete Box Culvert			
1:2:4 Concrete	19.6 C Y	@ \$ 22.14 Per C Y	\$ 433.94
Reinforcing Bars	1740.0 Lbs	.055¢ Per Lb	95.70
		Total	529.64
GRAND TOTAL FOR GROUP NO. 1.....		\$ 10,845.56	

GROUP NO. 2
SOUTH OF SAND SPRINGS

BRIDGE

In Section 27, T 19 N., R 11 E.		Drainage Area 1200 A Mountainous.	
26' x 8' x 20' I BM Bridge		Sta. 354 / 80	
1:2:3 Concrete	20.6 C Y	@ \$ 19.28 Per C Y	\$ 397.17
1:2:4 Concrete	64.0 C Y	@ \$ 19.46 Per C Y	1245.44
Reinforcing Bars	6400.0 Lbs	.0525¢ per Lb	336.00
Structural Steel	9835.0 Lbs.	.055¢ Per Lb	540.93
Reinf. Conc. Hand Rail	108.0 L F	1.00 Per L F	108.00
2 1/2" Black Iron Pipe	4.5 L F	.75¢ Per L F	3.38
		Total	\$2630.92

CULVERTS

In Section 27, T 19 N., R 11 E.		Drainage Area 25 A. Mountainous	
4' x 3' x 38' Concrete Box Culvert		Sta. 335 / 80	
1:2:4 Concrete	17.5 C Y	@ \$ 18.26 Per C Y	\$319.55
Reinforcing Bars	1540.0 Lbs.	.055¢ Per Lb.	84.70
		Total	\$404.25
In Section 26, T 19 N., R 11 E.		Drainage Area 25 A Mountainous	
4' x 3' x 38' Concrete Box Culvert		Sta 363 / 50	
1:2:4 Concrete	17.5 C Y	@ \$ 18.26 Per C Y	\$ 319.55
Reinforcing Bars	1540.0 Lbs.	.055¢ Per Lb.	84.70
		Total	404.25
In Section 26, T 19 N., R 11 E.		Drainage Area 40 A Mountainous	
5' x 3' x 30' Concrete Box Culvert		Sta. 376 /	
1:2:4 Concrete	17.3 C Y	@ \$ 18.26 per C Y	\$ 315.90
Reinforcing Bars	1500.0 Lbs	.055 Per Lb.	82.50
		Total	\$ 398.40
In Section 27, T 19 N., R 11 E.,		Drainage Area 6 A. Mountainous	
2' x 2' x 30' Concrete Box Culvert		345 /	
1:2:4 Concrete	8.3 C Y	@ \$ 19.46 Per C Y	161.52
Reinforcing Bars	730.0 Lbs	.055¢ Per Lb	40.15
			201.67