

the same and reconstruction of shoulders after completion of paving; cleaning out side ditches; etc. Square Yards to be paid for according to the number of Square Yards of paving laid. All payment for grading to be covered by the price for Fine Grading.

Approx. 23,800 Sq.Yds @ \$ 0.08 per Sq Yd. 1,904.00

Total Cost of Paving and otherwise improving Two (2) Miles on South Lewis \$ 54,978.00

TURKEY MOUNTAIN ROAD.

"From end of present pavement on Turkey Mountain road, south between Sections 2-3, 10-11, 1/2 mile between Sections 14-15, T 18 N., R 12 E. a distance of 2 1/2 Miles on Sec. "21" Mi. 4,5 and Pt.6".

APPROXIMATE QUANTITIES.

GRADING:

Approx. 900 C Y Earth Excavation @ \$ .37 per C Y \$ 333.00  
" 900 C Y Loose Rock Ex. @ 1.25 per C Y 1,125.00  
" 200 C Y Solid Rock Ex. @ 2.50 Per C Y 500.00  
" 600 C Y Earth Borrow @ .37 per C Y 222.00

PAVING:

Approximately Two and one-half (2 1/2) Miles of 20 foot 9"-7"-9", 1:2:3 1/2 Mixture Tulsa County Standard Modified Bates Type Lime-stone Cement concrete paving, including all metal, metal center strips, etc. Complete

Approx. 29,340 Sq.Yds @ \$2.26 per Sq.Yd. \$ 66,308.40

FINE GRADING:

Grading to subgrade, shaping and rolling the same and reconstruction of shoulders after completion of paving; cleaning out side ditches etc., Square Yards to be paid for according to the number of Square Yards of paving laid.

Approx. 29,340 Sq.Yds @ \$ 0.10 per Sq Yd. 2,934.00

TOTAL COST OF PAVING AND OTHER-WISE IMPROVING TWO AND ONE-HALF (2 1/2) Miles ON TURKEY MOUNTAIN. \$ 71,422.40

TOTAL COST OF PAVING AND OTHER WISE IMPROVING APPROXIMATELY FOUR AND ONE-HALF (4 1/2) MILES IN PROPOSAL NO. 6. \$ 126,400.40

Force Account, or Extra work, only when ordered in writing by the County Engineer, at ACTUAL COST, plus Fifteen (15%) per Cent.

If awarded the said work, we propose to immediately enter into contract, furnishing an acceptable Surety Company Bond, both contract and statutory, in the full amount of the contract price, agreeing to begin the said work within ten (10) days after work order is issued by the County Engineer, and to complete the same to your acceptance within One Hundred and twenty (120) days after receiving said work order, BUT, IT IS THE SPECIFIC UNDERSTANDING THAT WORK ORDER WILL NOT BE ISSUED UNTIL FUNDS ARE AVAILABLE FOR THE PAYMENT OF THE ABOVE WORK.

Upon failure to complete within the time limit as proposed, we agree to the provisions as embodied in the Oklahoma State Standard Specifications respecting failure to so complete.

When mutually agreed to by and between your Honorable Board and ourselves, this proposal may be considered for extension to additional work of the same character and upon the same highway and as a continuation of the work herein bid upon as though the same were herein originally contained and set out.

Certified Check or Bidder's Bond amounting to \$15,000.00 being approximately ten (10%) per cent of the sum bid and conforming to the requirements of the specifications and "Notice to Contractors", is hereto attached.

Respectfully submitted this 24th. day of June, 1929.

1011-1016 Daniels Bldg. Tulsa, Okla.

HIGHWAY CONST. CO. Contractor.  
By: Mat X Beard, V.Pres.

PROPOSAL FOR CONSTRUCTION OF DRAINAGE STRUCTURES.

BIXBY-GLENN POOL, SOUTH OF HILLTOP.

Proposal No. 7.  
Commissioners Resolution No. 9.  
Letting June 24, 1929.