

Bet. Sec. 24-25, Twp. 19 N., R 13 E. Drainage Area 8 A. Fast Rolling.  
 2' x 2' x 30' Concrete Box Culvert - BC - 5

1:2:4 Concrete	8.5 C Y @	\$22.50 Per C Y	\$191.25
Reinforcing Steel	727 Lbs @	.0525 Per Lb.	38.17
		Total	\$229.42

Bet. Sec. 24-25, Twp. 19 N., R 13 E. Drainage Area 7 A. Fast Rolling  
 32' - 18" Reinforced Concrete Pipe

1:2:4 Concrete	2.1 C Y @	\$25.00 C Y	\$ 52.50
Reinforcing Steel	33 Lbs. @	.06 Per Lb	1.98
Laying Pipe	32 L F @	1.75 Per L F	56.00
(Pipe to be furnished County at site)		Total	\$110.48

Bet. Sec. 24-25, Twp. 19 N., R 13 E. Drainage Area 640 A. Fast Rolling.  
 2-8' x 4' x 30' Concrete Box Culvert - BC - 5-A

1:2:4 Concrete	60.8 C Y @	\$21.50 Per C Y	\$1307.20
Reinforcing Steel	5230 Lbs. @	.05 Per Lb.	261.50
	Total	\$ Total	1568.70

Bet. Sec. 19-30, Twp. 19 N., R 14 E. Drainage Area 20 A. Fast Rolling.  
 2' - 6" x 2' x 30' Concrete Box Culvert - BC - 5

1:2:4 Concrete	9.4 C Y @	\$22.50 Per C Y	\$211.50
Reinforcing Steel	790 Lbs. @	.0525 Per Lb.	41.48
		Total	\$252.98

Bet. Sec. 19-30, Twp. 19 N., R 14 E. Drainage Area 10 A. Fast Rolling.  
 2' x 2' x 30' Concrete Box Culvert - BC - 5

1:2:4 Concrete	8.5 C Y @	\$22.50 Per C Y	\$191.25
Reinforcing Steel	727 Lbs.	.0525 Per Lb	38.17
		Total	\$229.42

GRAND TOTAL FOR PROPOSAL \$4839.22

Force Account or Extra Work, only when ordered by the Engineer, at actual cost plus 15 per cent.

If awarded the work, we agree to immediately enter into contract, furnishing an acceptable Surety Company Bond, both contract and statutory, in the full amount of 100% of the estimated contract price, agreeing to begin the said work within ten (10) days from this date, and to complete the same on or before the 1st. day of September, 1927, and upon failure to do so, agree to the provisions as embodied in the Oklahoma Standard Specifications respecting failure to complete work within the specified time as bid.

When mutually agreed to by and between your Honorable Board and ourselves, this proposal may be considered for extension to additional work of the same character and upon the same highway, and as a continuation of the work herein bid upon as though the same were herein originally contained and set out.

Bidders Bond amounting to \$502.50 being approximately 10% of the sum bid is hereto attached, conforming to the "Notice to Contractors", and specification provisions.

Respectfully Submitted on this 6th. day of June, 1927.

E G Fike and Co. Contractor.

By: E G Fike, Pres.

The unsuccessful Bidders on the above project were:  
 None.

The Bid of E G Fike and Co. in the sum of \$12,685.58 on Project No. 5, being the lowest and best bid, it was moved and ordered that Contract be awarded the said E G Fike and Co. in the amount of their bid as shown by copy of proposal which follows:

Honorable County Commissioners  
 Tulsa County, Oklahoma.

Letting June 6th. 1927  
 Proposal No. 5.

Gentlemen:

The undersigned, having examined the plans and specifications, the location and character of the work proposed to be done and performed in the construction of the herein listed culverts and bridges, proposes to furnish all labor, materials and equipment and to complete the same according to the plans and specifications and to the stakes and under the direction of the County Engineer or his duly authorized representatives, which price as bid includes all excavation and the structure complete and in place (Oklahoma Standard Specifications to govern) the following structures at the unit item prices set opposite, viz, to-wit:

Between Sec. 34-35, T. 19 N., R 12 E

Mile Three (3) Section "Z 1" Drainage Area 150 A. Light Hilly.  
 8' x 4' x 33' (Skewed) Concrete Box Culvert - BC-5

1:2:4 Concrete	36.0 C Y @	\$18.50 Per C Y	\$666.00
Reinforcing Steel	3040 Lbs. @	.05 Per Lb	152.00
		Total	\$818.00

Mile Three (3) Section "Z 1" Drainage Area 2500 A. Fast Hilly  
 40' x 7' x 20' I-BM Bridge (Heavy Excavation)

1:2:3 Concrete	31.0 C Y @	\$19.50 Per C Y	\$604.50
1:2:4 Concrete	95.0 C Y @	18.50 Per C Y	1757.50