Mile 4, Section "JJ" - Station 195 / 20
38' x 11' x 30' (Skewed) I Bm Bridge — Drainage Area 5½ Sq. Miles Light Hilly.

1:2:4 Conc. in Abuts.	158.0 C Y	@	$19.50 Per C Y	$ 3081.00
1:2:3 Conc. in Floor	40.0 C Y	@	$20.35 Per C Y	814.00
Reinforcing Steel	18,000. Lbs	@	.05 Per Lb.	900.00
Structural Steel	32,200. Lbs.	@	.047 Per Lb.	1513.40
Precast R C Handrail	86.0 L F	@	1.50 Per L F	129.00
3" Round Blk.Pipe Drains	25.0 L F	@	.20 Per L F	5.00
2½" Rd.Blk.Pipe Drains	12. L F	@	.20 Per L F	2.40
			Total	$ 6444.80

Mile 3, Section "JJ" - Sta. 110 / 65
Bet. Sec. 2-11 T 19 N., R 13 E. — Drainage Area 10 A Mountainous.
3' x 2' x 36' Concrete Box Culvert -BC -5

1:2:4 Concrete	13.0 C Y	@	$20.00 Per C Y	$260.00
Reinforcing Steel	1035. Lbs.	@	.05 Per Lb	51.75
			Total	$311.75

Mile 3, Section "JJ", Sta. 118 / 16
Bet. Sec.2-11, T 19 N., R 13 E. — Drainage Area 10 A Mountainous.
3' x 2' x 57' Concrete Box Culvert -BC -6

1:2:4 Concrete	18.0 C Y	@	$20.00 Per C Y	$360.00
Reinforcing Steel	1449 Lbs	@	.05 Per Lb.	72.45
			Total	$432.45

Mile 3, Section "JJ", Sta. 126 / 10
Bet.Sec. 2-11, T 19 N., R 13 E. — Drainage Area 5 A Mountainous
2' x 2' x 62' Concrete Box Culvert - BC -6

1:2:4 Concrete	16.5 C Y	@	$20.00 Per C Y	$330.00
Reinforcing Steel	1350. Lbs	@	.05 Per Lb	67.50
			Total	$397.50

Mile 3, Section "JJ" - Sta. 141 / 68
Bet. Sec. 2-11, T 19 N., R 13 E. — Drainage 7 A Fast Rolling
2' x 2' x 32' Concrete Box Culvert - BC -5

1:2:4 Concrete	8.8 C Y	@	$20.00 Oer C Y	$176.00
Reinforcing Steel	766. Lbs.	@	.05 Per Lb.	38.30
			Total	$214.30

Mile 3, Section "JJ" - Sta. 148 / 85
Bet. Sec. 2-11, T 19 N., R 13 E. — Drainage Area 3 A. Mountainous.
2' x 2' x 46' Concrete Box Culvert -BC - 6

1:2:4 Concrete	13.0 C Y	@	$20.00 Per C Y	$260.00
Reinforcing Steel	1036 Lbs.	@	.05 Per Lb.	51.80
			Total	311.80

Mile 4, Section "JJ" - Sta 167 / 70
Bet. Sec. 1-12, T 19 N., R 13 E. — Drainage Area 30 A. Rolling
3' x 2'-6" x 36' Concrete Box Culvert - BC-5

1:2:4 Concrete	12.7 C Y	@	$19.50 Per C Y	$247.65
Reinforcing Steel	1045 Lbs.	@	.05 Per Lb.	52.25
			Total	$299.90

Mile 4, Section "JJ" - Sta. 187 / 00
Bet.Sec. 1-12, T 19 N., R 13 E. — Drainage Area 15 A. Rolling.
2' x 2' x 40' Concrete Box Culvert - BC - 6

1:2:4 Concrete	10.3 C Y	@	$20.00 Per C Y	$206.00
Reinforcing Steel	920. Lbs	@	.05 Per Lb.	46.00
			Total	$252.00

Mile 5, Section "JJ" - Sta. 234 / 95
Bet.Sec. 6-7, T 19 N., R 14 E. — Drainage Area 25 A. Rolling.
3' x 2' x 34' Concrete Box Culvert -BC -5

1:2:4 Concrete	10.9 C Y	@	$20.00 Per C Y	$218.00
Reinforcing Steel	943 Lbs.	@	.05 Per Lb.	47.15
			Total	$301.33

Mile 5, Section "JJ" - Sta. 256 / 50
Bet. Sec. 6-7, T 19 N., R 14 E. — Drainage Area 35 A Rolling
3' x 2'-6" x 42' Concrete Box Culvert - BC - 6

1:2:4 Concrete	14.1 C Y	@	$20.00 Per C Y	$282.00
Reinforcing Steel	1189. lbs.	@	.05 Per Lb	59.45
			Total	$341.45

Mile 5, Section "JJ" - Sta. 261 /50
Bet. Sec. 6-7, T 19mN. R 14 E. D — Drainage Area 1250 A. Rolling.
Double 8' x 8' x 30' Concrete Box Culvert - BC - 5A
(Channel Change)

1:2:4 Concrete	92.7 C Y	@	$18.75 Per C Y	$1738.13
Reinforcing Steel	6988 Lbs.	@	.05 Per Lb.	349.40
			Total	$$2087.53

GRAND TOTAL FOR PROPOSAL $24,834.71

Force Account or Exta Work only when ordered by the Engineer at actual cost plus 15% PerCent.