

(No. 313) FIRE DEPARTMENT CONNECTIONS:

COMPARED

One Two-way Fire Department connection, located on Cheyenne Street, wall pattern and connected to system.

(No. 500-503) UNDERGROUND PIPE & FITTINGS:

Furnish cast iron supply pipe from curb line on Cheyenne Street into building, at rear of vault, and connect to sprinkler system. If for any reason it becomes necessary to install the underground piping at a depth greater than 4 ft. or if water, quick-sand, rock or other unforeseen obstructions are encountered, or shoring is required, you are to pay for, as an extra to the contract price, the additional expense involved.

(No. 514) CITY WATER CONNECTION:

You to furnish 6" City Water Supply connections at curb, including meter if required. Work to begin at 6" Bell outlet provided by you in plumb and level position at point designated by us,

(No. 601) FREIGHT-TEAMING:

Deliver materials at your freight station or railroad siding; do all local teaming and handling.

(No. 610) MASON AND CARPENTER WORK:

Provided all necessary openings for proper installation of the work specified in foundations, walls, floors, ceilings, partitions, stairways, etc. including all patching and repairing required.

No. 611) TRENCH WORK:

Necessary trench work for the proper installation of underground piping including excavating, preparing of trenches, and back filling.

(No. 612) PAINTING:

Paint the sprinkler piping in Office Section only with two coats of paint to match ceiling.

EXTRA MATERIAL AND LABOR:

It is mutually understood and agreed that all additional sprinklers or other extra material or other extra materials and labor required on account of alterations or additions to the premises, or obstructions along the ceiling not in position, or shown on plans furnished us, when our survey was made, are to be considered as work additional to that covered by contract, and will not be included under the "more or less sprinkler" clause on face of contract, but is to be paid for by you as an extra to the contract price.

No. 110 Open Sprinklers.

A system of Rockwood Open Sprinklers installed on north side of building and front building 3 sprinklers and 2 sprinklers on rear building west side making $1\frac{1}{2}$ connection to sprinkler system with necessary controlling valves and draw-off piping. All pipe on system side of controlling valve, and all fittings and hangers outside of buildings, to be galvanized.

9. The Owner warrants unto the Contractor that the Owner is the sole and unconditional Owner of the premises described in paragraph I hereof in absolute fee simple title, subject to no incumbrance or lien except a mortgage for-----None Dollars, dated-----, given to----- maturing-----

10. The Contractor may at any time assign all or any part of its rights under this agreement.

11. This contract must be signed by an officer of the Contractor and shall be binding upon the heirs, administrators, successors and assigns of the parties hereto.

12. Should not more than five per cent (5%) more or less than One Hundred Sixty (160) sprinklers be required, they shall be charged or credited at Six Dollars (\$6.00) Dollars each.

Prices on a greater difference than five per cent (5%) shall be agreed upon.